



EDINBURG CISD

PURCHASING DEPARTMENT

411 N. 8th Ave., Edinburg, TX 78541

(956) 289-2311, (956) 38-7687

DOMINGA "MINGA" VELA, President
CARMEN GONZÁLEZ, Vice President
OSCAR SALINAS, Secretary
LUIS ALAMIA, Member
MIGUEL "MIKE" FARIAS, Member
LETICIA "LETTY" GARCIA, Member
XAVIER SALINAS, Member

Dr. Mario H. Salinas, Superintendent

ADDENDUM 2

CSP 22-68

Memorial Middle School Heating & Air Condition (HVAC) Improvements Funded through the Elementary & Secondary Emergency Relief (ESSER) Funds

April 8, 2022

I. INSTRUCTIONS:

A. The following changes, omissions or alterations to the specification and drawings shall be made insofar as the specifications and drawings are inconsistent with following, this addendum shall govern.

B. Acknowledge receipt of this addendum by inserting its number and date of issue in the place provided for same in the proposal. This addendum forms a part of the Contract Documents.

C. It is imperative that this addendum be inserted INTO set of specifications.

II. SEE ADDENDUM BELOW:

SPECIFICATIONS

Item 01 Specification 23 73 13 – Modular Central Station Air Handling Units

A. Replace specification section in its entirety.

DRAWINGS

Item 02 SHEET M0.01 – MECHANICAL LEGEND

A. Added general note 23.

Item 03 SHEET MD2.12F – LEVEL 1 MECHANICAL DEMO PLAN – F.

A. Revised keyed notes 2 and 3.

Item 04 SHEET MD2.13G – LEVEL 1 MECHANICAL DEMO PLAN – G.

A. Replaced keyed note 4 with keyed note 3 for EXRTU-19 and EXRTU-20.

Item 05 SHEET MD3.12 – ENLARGED MECHANICAL DEMO PLAN

A. Revised keyed notes 3 and 10.

Item 06 SHEET MD3.13 – ENLARGED MECHANICAL DEMO PLAN

A. Scheduled cooling tower 3-way valve to be demolished.

B. Clarified that the chillers and cooling towers to remain.

C. Revised keyed note 6.

Item 07 SHEET M1.11 – COMPOSITE LEVEL 1 MECHANICAL HYDRONIC PIPING PLAN

A. Added differential pressure sensor.

Item 08 SHEET M2.11A – LEVEL 1 MECHANICAL PLAN - A

A. Revised keyed note 1.

Item 09 SHEET M2.11B – LEVEL 1 MECHANICAL PLAN - B

A. Revised keyed note 1.

Item 10 SHEET M2.11C – LEVEL 1 MECHANICAL PLAN - C

A. Revised keyed note 1.

Item 11 SHEET M2.11D – LEVEL 1 MECHANICAL PLAN - D

A. Revised keyed note 1.

Item 12 SHEET M3.10 – ENLARGED MECHANICAL ROOM PLANS

A. Revised view of enlarged mechanical room plan #5.

Item 13 SHEET M3.11 – ENLARGED MECHANICAL ROOM PLANS

A. Replaced keyed note 5 with keyed note 10 on LEVEL 2A MECHANICAL AHU-8.
B. Revised view of LEVEL 2B MECHANICAL AHU-9.
C. Revised view of LEVEL 2B MECHANICAL AHU-10.

Item 14 SHEET M3.13 – ENLARGED MECHANICAL ROOM PLANS

A. Corrected title block.
B. Added control valves to condenser water at chillers.
C. Revised keyed note 9.

Item 15 SHEET M4.02 – MECHANICAL CONTROLS

A. Revised Single Zone VAV Air Handling Unit – Control Schematic and Sequence of Operations.
B. Revised Multi Zone VAV Air Handling Unit – Control Schematic and Sequence of Operations.

Item 16 SHEET M4.03 – MECHANICAL CONTROLS

A. Revised Chilled Water System – Variable Primary Flow – Control Schematic Sequence of Operations
B. Revised Condenser Water System – Chiller Plant – Control Schematic and Sequence of Operations

Item 17 SHEET M5.01 – MECHANICAL SCHEDULES

A. Revised fan schedule.
B. Revised packaged dx roof top unit schedule

Item 18 SHEET M5.02 – MECHANICAL SCHEDULES

A. Removed duplicate details #7 and #8.

Item 19 SHEET M6.01 – MECHANICAL SCHEDULES

A. Corrected detail numbering.

Item 20 SHEET EP2.11C – LEVEL 1 ELECTRICAL POWER PLAN - C

A. Added distribution panel DP-C.

Item 21 SHEET EP2.12G – LEVEL 1 ELECTRICAL POWER PLAN - G

A. Showed location of existing panel CK.

Item 22 SHEET E3.01 – ELECTRICAL ENLARGED POWER PLANS

A. Added power for Refrigerant Monitoring Panel and chiller valves.

Item 23 SHEET E4.01 – ELECTRICAL ONE-LINE DIAGRAM

A. Added distribution panel DP-C.
B. Revised the feeding of branch circuit panels MC1, MC2, MD1, MD2, MF1 and MG1.

Item 24 SHEET E5.01 – ELECTRICAL SHCEDULES

A. Revised the parameters of panels MC1 and MD1.

Item 25 SHEET E5.02 – ELECTRICAL SHCEDULES

A. Revised the parameters of panel MG1.

REQUEST FOR INFORMATION

Item No. 26- Project Schedule:

A. There is no pre-established project schedule or phasing plan for the project. The Contractor shall be responsible for submitting a phasing plan and project schedule prior to construction. Such plans are subject to review and approval by Owner.

Item No. 27 - Project Completion:

A. The proposed project term is to be included in the bid form by the Contractor and subject to Owner evaluation.

Item No. 28 - Roof Warranty:

A. There is no current roof warranty for this campus.

Item No. 29 - Asbestos Report:

A. PLM Summary Report – See attached.



© 2007 Europa Technologies
© 2007 Tele Atlas

© 2007 Google™

Point: 26°19'25.70"N 98°07'39.15"W Elev: 79 ft

Streets: 100%

Elev: 1887 ft

PLAT SHOWING:

40.00 Ac. (39.97 Ac.)

BEING ALL OF LOT 11, SECTION 248,
TEXAS MEXICAN RAILWAY COMPANY SURVEY,
(VOL. 3, PG. 6, H.C.M.R.)
HIDALGO COUNTY, TEXAS.



FEB 12 1990

Precoated SIGNATURE® 200 Panel LIMITED WARRANTY

Metal Building Components, Inc. warrants the panels, effective from the date of shipment, will perform in accordance to the following Signature® 200 Warranty:

PERFORMANCE SUMMARY

FILM INTEGRITY: The paint film WILL NOT crack, check, blister, peel, flake or chip for a period of twenty (20) years for Sidewall and Roof panels. Cracking is defined as breaks in the flat coating as opposed to breaks in the film caused by metal forming, which is not warranted hereunder.

CHALK RATING

YEARS	SIDEWALL Inclined 0°-15°	ROOF Inclined 16°-86°	ASTM
5	8	8	D659
10	8	8	D659
20	8	6	D659

FADE--E (HUNTER) UNITS

YEARS	SIDEWALL Inclined 0°-15°	ROOF Inclined 16°-86°	ASTM
5	5	5	D2244
10	5	5	D2244
20	5	8	D2244

TERMS AND CONDITIONS

FAILED MATERIAL — If the panel finish fails to perform as indicated under the terms of Performance outlined above, MBCI shall have no liability with respect thereto except, at its sole option to repaint, replace, or restore the failed material, which shall be the purchaser's sole and exclusive remedy. Repainting shall not necessarily be Signature® 200. In no event, however, shall MBCI's responsibility extend to any consequential damages and in all cases MBCI reserves the right to approve and negotiate the contract for such repainting, replacing or restoring. The warranty on any repainted, replaced or restored coated material supplied hereunder shall be for the unexpired portion of the warranty period applicable to the original panel.

CLAIMS — Claims must be reported in writing to MBCI within thirty (30) days after discovery of nonconformance, rupturing, perforating or structurally failing sheet or for any special, indirect, or consequential loss of profits or any other incidental, general, special or compensatory damages to anyone by reason of the fact that such panels shall have been nonconforming, rupturing, perforating, or structurally failing. Adequate identification of the material involved in the claim, including date of installation, MBCI order number, invoice number, and date of shipment must be established by Buyer. A copy of this document must be presented to MBCI at time of claim. All notices given under or pursuant to this Agreement shall be in writing and sent by registered mail, postage prepaid, return receipt requested to:

Metal Building Components, Inc.
P. O. Box 38217
Houston, Texas 77238
Attn: A. R. Ginn/President

Precoated SIGNATURE® 200 Panel LIMITED WARRANTY

ADDITIONAL WARRANTY LIMITATIONS -

- A. This warranty covers the material exposed to normal atmospheric conditions (which term excludes corrosive or aggressive atmospheres such as, but not limited to, those contaminated with chemical fumes or direct salt spray) in the continental United States or Canada, unless MBCI agrees otherwise in writing. This warranty shall not apply where material failure is the result of fire, other accident or casualty, vandalism, salt spray, atomic radiation, harmful fumes or foreign substances in the atmosphere, acts of God, or other such occurrences beyond MBCI's control.
- B. This warranty will not extend to or cover damages to the material due to improper packaging, shipping or processing as specified in the National Coil Coaters Association Technical Bulletin No. IV-7, improper handling (whether pre-erection or during erection), improper storage, improper erection, or improper installation (which includes failure to permit drainage of standing water.)
- C. Microscopic crazing of the film on outside radii is considered normal and is not to be construed as film cracking.
- D. This warranty does not apply in the event of deterioration to the panels caused directly or indirectly by panel contact with inferior fasteners. Selection of suitable long-lasting fasteners to be used with MBCI extended life panels rests solely with the Purchaser.
- E. This warranty will not extend to or cover:
 - (a) Damage to the coating occasioned by moisture or other contaminations detrimental to the coating.
 - (b) Water damage to any materials after they leave the possession of MBCI.
 - (c) Damage to the prepainted metal caused by shipping, handling, and/or installation, storing, erecting and/or handling of the panels on the job site and/or any act or acts of negligence of the customer or any third party after the panels leave the possession of MBCI.
 - (d) Damage to the prepainted metal caused by cascading water.
- F. Customer shall exercise diligence in inspection of materials as received from MBCI prior to use so as to mitigate expense involved to MBCI under this warranty.
- G. This warranty does not apply to the interior or reverse side finish nor does it extend to pre-painted materials used in interior (not atmospherically exposed) applications.
- H. Panels repainted, replaced or otherwise restored under this warranty shall not extend the original warranty expiration date as applicable hereunder.
- I. This warranty applies only to the paint film on the material and does not cover in any way any other aspect of the material.

ASSIGNMENT — This warranty shall extend to the purchaser of the material and is non-assignable and/or non-transferable. Should the Purchaser become insolvent, bankrupt, make an assignment for the benefit of its creditors, or for any reason discontinue its normal or regular business practices, this warranty shall forthwith become null and void and of no legal effect.

EXCEPT AS SET FORTH HEREIN, MBCI MAKES NO OTHER WARRANTIES, EXPRESS OR IMPLIED, LIMITED OR OTHERWISE, INCLUDING ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, WITH RESPECT TO THE MATERIAL. In no way shall MBCI be responsible for any loss of profit or any other incidental, general, special, compensatory or consequential damages resulting from the failure of the material covered by this warranty.

The laws of the State of Texas shall govern the rights and duties of the parties under this agreement and jurisdiction and venue is fixed in Harris County, Texas.

This Warranty is the full and complete agreement of the parties and shall not be modified, altered or extended except in writing signed by the President of MBCI.

Signature® 200 is a registered trademark of Metal Building Components, Inc.

**EDINBURG ISD - EDINBURG MIDDLE SCHOOL
CHILLER RD. EDINBURG, TEXAS**

S5-4102

Project Name

MBCI Job #

COLONY GREEN

Color(s)

2/7/96

Date

Sheron Henshaw

Credit Department

Metal Building Components, Inc.





BARE GALVALUME® 20 YEAR LIMITED WARRANTY

Metal Building Components, Inc. warrants the panels will perform in accordance to the following Bare GALVALUME® Warranty:

MBCI's hot dipped aluminum-zinc alloy coated GALVALUME® sheet steel sold for use as unpainted steel building roofing and siding panels, if erected within the United States WILL NOT rupture, fail structurally, or perforate within a period of 20 years from date of shipment due to exposure to normal atmospheric corrosion.

THIS WARRANTY DOES NOT APPLY to sheets exposed at any time to corrosive or aggressive atmospheric conditions, including but not limited to:

1. Areas subject to salt water marine atmospheres or to constant spraying of either salt or fresh water.
2. Areas subject to fallout or exposure to corrosive chemicals, fumes, ash, cement dust, or animal waste.
3. Areas subject to water run-off from lead or copper flashings or areas in metallic contact with lead or copper.
4. Conditions/circumstances where corrosive fumes or condensates are generated or released inside the building.

This warranty DOES NOT APPLY in the event of:

- A. Degree of bending less than 2T for sheet gauges up to 0.030 in. and degree of bending less than 4T for sheet gauges 0.031 in. and thicker.
- B. Slopes of roof or sections of the roof flatter than 1/4:12.
- C. Mechanical, chemical, or other damage sustained during shipment, storage, forming, fabrication, during or after erection.
- D. Forming which incorporates severe reverse bending or which subjects coating to alternate compression and tension.
- E. Failure to provide free drainage of water, including internal condensation, from overlaps and all other surfaces of the sheets or panels.
- F. Failure to remove debris from overlaps and all other surfaces of the sheets or panels.
- G. Damage caused to the metallic coating by improper scouring or cleaning procedures.
- H. Deterioration of the panels caused by contact with green or wet lumber or wet storage stain caused by water damage or condensation.
- I. Presence of damp insulation or other corrosive materials in contact with or close proximity to the panel.
- J. This warranty does not apply in the event of deterioration to the panels caused directly or indirectly by the panel contact with fasteners. Selection of suitable long-lasting fasteners to be used with GALVALUME® roofing and siding panels rests solely with the Buyer.

BARE GALVALUME® 20 YEAR LIMITED WARRANTY

This warranty shall be subject to the stipulations, limitations, and conditions hereinafter set forth:

1. MBCI's liability for breach of this warranty shall be limited exclusively to the cost of either repairing or replacing nonconforming, rupturing, perforating, or structurally failing panels.
2. MBCI shall not in any event be liable for the cost of labor expended by others on any nonconforming, rupturing, perforating or structurally failing sheet or for any special, indirect, or consequential loss of profits or any other incidental, general, special or compensatory damages to anyone by reason of the fact that such panels shall have been nonconforming, rupturing, perforating, or structurally failing.
3. This warranty will not extend to or cover damages to the material due to shipping, improper handling (whether pre-erection or during erection), improper storage, improper erection, or improper installation (which includes failure to permit drainage of standing water.)
4. Claims must be reported in writing to MBCI within thirty (30) days after discovery of nonconformance, rupture, perforation, or structural failing, and MBCI shall be given a reasonable opportunity (which shall not be less than thirty (30) days from the date of receipt of notification) to inspect the panels claimed to be nonconforming, rupturing, perforating, or structurally failing. Adequate identification of the material involved in the claim, including date of installation, MBCI order number, invoice number, and date of shipment must be established by Buyer. A copy of this document must be presented to MBCI at time of claim.
5. Buyer shall exercise diligence in inspection of sheets as received from MBCI so as to mitigate any expenses to MBCI under this warranty.
6. This warranty shall extend to the purchaser of the material and is non-assignable and/or non-transferable. Should the Buyer become insolvent, bankrupt, make an assignment for the benefit of its creditors, or for any reason discontinue its normal or regular business practice, this warranty shall forthwith become null and void and of no legal effect.
7. MBCI reserves the right to terminate this warranty at any time (except as to orders already accepted) upon the giving of written notice thereof.
8. Panel repaired or sheet product furnished under this warranty shall not extend the original warranty time period hereunder.
9. The laws of the State of Texas shall govern the rights and duties of the parties under this agreement and jurisdiction and venue is fixed in Harris County, Texas.
10. This warranty is the full and complete agreement of the parties and shall not be modified, altered or extended except in writing and signed by an authorized agent of MBCI and the Buyer.
11. All notices given under or pursuant to this Agreement shall be in writing and sent by registered mail, postage prepaid, return receipt requested, to:
Metal Building Components, Inc.
P. O. Box 38217
Houston, Texas 77238
Attn: A. R. Ginn/President

MBCI MAKES NO GUARANTEES OR WARRANTIES, EITHER EXPRESS OR IMPLIED, LIMITED OR OTHERWISE, EXCEPT AS SET FORTH HEREIN INCLUDING, WITHOUT LIMITATION, WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE AND SHALL HAVE NO OTHER LIABILITY WITH RESPECT THERETO.

GALVALUME® is a registered trademark of BIEC International Inc.
EDINBURG MIDDLE SCHOOL - CHILLER BUILDING
DOOLITTLE RD. - EDINBURG, TEXAS

Project Name

Sharon Henshaw

Credit Department

Metal Building Components, Inc.

S4-12110

MBCI Job #

6/14/95

Date





JUN 15 RECD

UL 90 CERTIFICATE

Name Edinburg Middle School Date 6-14-95

Address Doolittle Rd City Edinburg

File Number _____

THIS CERTIFIES that the roof deck components manufactured by Metal Building Components, Inc. on the building indicated above have been fabricated according to specifications for Construction No. 161 Class 90 as prescribed in the Underwriter's Laboratories Building Material List.

MBCI Job #S4-012110
Edinburg ISD/Edinburg Middle School
Chiller Bldg./Doolittle Rd
Edinburg, TX

[Signature]
Name
Vice President/Marketing
Title
Metal Building Components, Inc.
Manufacturer or Authorized Representative
P. O. Box 38217
Address
Houston TX
City State
77238 6/6/95
Zip Code Date

MBCI Coil #10880

THIS CERTIFIES that the roof deck assembly on the building indicated above has been installed and anchored to the building according to good engineering practices and specifications for Construction No. 161 Class 90 as prescribed in Underwriter's Laboratories Building Material List.

[Signature]
Name
AUTHORIZED AGENT
Title
TRI City Steel
Company Name
P.O. Box 733
Address
Pharr TX
City State
78577 6-14-95
Zip Code Date

oh



Kynar 500® or Hylar 5000™ Limited Warranty

Berridge Manufacturing Company warrants that *Kynar 500®* or *Hylar 5000™* 70% full-strength Fluoropolymer finish will perform for Twenty (20) years from date of installation as an effective surfacing material within the scope of the conditions and limitations defined in this warranty document:

EFFECTIVE SURFACING MATERIAL IS DEFINED TO MEAN:

- A. Freedom from cracking, chipping or peeling due to the deterioration of the finish for a period of twenty (20) years from date of purchase, exclusive of mechanical damage or other abnormal contingencies. (See Para 2).
- B. Freedom from any color changes in excess of 5 NBS Units (Using the NBS unit of color notation as measured on the MEECO Colormaster: ASTM-D-2244) for a period of twenty (20) years from date of purchase.
- C. Freedom from chalking in excess of Number 8 Rating (ASTM-D-659-80) for a period of twenty (20) years from date of installation

MATERIAL DESCRIPTION: PATINA GREEN COIL, SEAMS, FLATS

SOLD TO: _____ **JOB:** _____

BOWMAN DISTRIBUTING CO, INC. EDINBURY MIDDLE SCHOOL
4201 SOUTH EXPRESSWAY 83
P.O. BOX 1134 DOOLITTLE & RUSSELL RD.

HARLINGEN, TEXAS 78551 EDINBURY, TEXAS

INVOICE: #102581, 102128, 101267
101318, 99606, 97894 **EFFECTIVE DATE:** MAY 7, 1995

Jack A. Berridge OCTOBER 18, 1995
JACK A. BERRIDGE, PRESIDENT **DATE**

NOTE: THIS LIMITED WARRANTY IS SUBJECT TO THE TERMS, CONDITIONS AND LIMITATIONS WHICH ARE STATED ON THE REVERSE SIDE OF THIS WARRANTY.

© 1995 BERRIDGE

© 1995 BERRIDGE

OCT 20 1995



BOWMAN DISTRIBUTING COMPANY, INC.

SINCE 1949

P.O. BOX 1134 - 4201 S. EXPRESSWAY 83 - HARLINGEN, TEXAS 78551
(210) 423-6002 • FAX (210) 425-1792

Re: EDINBURG MIDDLE SCHOOL

10-YEAR WATER TIGHTNESS LIMITED WARRANTY

Bowman Dist. Co., Inc. whose signature appears below ("Bowman,") warrants to the original Building Owner ("owner") that, subject to each and every term(s), condition(s), limitation(s), allocation(s) of warranty and responsibility(ies) stated herein, Bowman's workmanship on the above named building will be adequate to prevent leaks for 10 years commencing with the date of completion of installation of the Roofing System. This warranty will be fully satisfied by repair of the Roofing System, and any such repairs shall carry a warranty against leaks only for the then remaining balance of the original 10-year Warranty period.

- ◆ BOWMAN MAKES NO OTHER WARRANTY WHATEVER, EXPRESS OR IMPLIED. ALL EXPRESSED OR IMPLIED WARRANTIES OF MERCHANTABILITY AND ALL EXPRESSED OR IMPLIED WARRANTIES OF FITNESS FOR ANY PARTICULAR PURPOSE WHICH EXCEED OR DIFFER FROM THE WARRANTIES HEREIN EXPRESSED OR IMPLIED ARE DISCLAIMED AND EXCLUDED FROM THIS 10-YEAR WATER TIGHTNESS LIMITED WARRANTY.

The Roofing System is defined as the furnished roof sheeting and related items used to fasten the roof sheeting to the roof structure.

IN NO EVENT SHALL BOWMAN HAVE ANY LIABILITY FOR ANY COMMERCIAL LOSS, CLAIMS FOR LABOR OR CONSEQUENTIAL DAMAGES OF ANY TYPE, WHETHER OWNER'S CLAIM BE BASED ON CONTRACT, TORT, WARRANTY, STRICT LIABILITY, OR OTHERWISE. IT IS EXPRESSLY AGREED THAT OWNER'S REMEDIES AFFORDED HEREUNDER ARE OWNER'S EXCLUSIVE REMEDIES.

TERMS, CONDITIONS, LIMITATIONS

1. Owner shall provide Bowman with written notice within ninety (90) days of the discovery of any leak(s) in the Roofing System. Failure of Owner to do so shall automatically relieve Bowman of any and all responsibility and/or liability under this 10-year Water Tightness Limited Warranty.

BRAUER PANEL - METAL ROOFING - STORE FRONTS - CANOPIES - CARPORTS - HANDRAILS

2. If, upon Bowman's inspection, Bowman determines that the leaks in the Roofing System are caused by defects in the Roofing System, Bowman's Roofing System repair obligation shall then arise in accordance herewith, but Owner's remedies and Bowman's liability shall in any event be limited to repair of the Roofing System. If Bowman should determine that such leaks are caused in whole or in part by some event or condition other than by defects in the roofing system, Bowman shall so notify Owner in writing within ten (10) days following the completion of such inspection. In such event, Bowman may either (a) proceed to effect the repairs necessary to restore the roofing system to a water tight condition without waiver of its right to recover the customary and usual costs and expenses of performing any necessary repairs, or, (b) select a Registered Professional Engineer with reasonably extensive experience in roofing technology, who along with a similarly qualified person selected by Owner, will jointly select a third party possessing qualifications acceptable to Bowman's and Owner's representatives. Such third party, together with the two representatives, shall then by majority determination establish the cause of the leaks and the extent of Bowman's responsibility for their repair, which determination shall be binding on the parties.

3. Bowman shall have no liability or responsibility under or in connection with this 10 Year Water Tightness Limited Warranty or the Roofing System, if any one or more of the following shall occur:

- a. Deterioration caused by marine (salt water) atmosphere or by regular spray of either salt or fresh water.
- b. Corrosion caused by heavy fallout or exposure to corrosive chemical, ash or fumes from any chemical plant, foundry, plating works, kiln, fertilizer manufacturing, paper plant, aviation fuel or the like.
- c. Deterioration caused by any corrosive substance or any condensate of any harmful substances contained, generated or released inside the building.
- d. Damage caused by worker(s), other than Bowman's workers, to the Roofing System.
- e. Any other cause beyond the control of Bowman.
- g. If, after installation of the Roofing System by Bowman, alterations, including, but not limited to, structures, fixtures, or utilities are placed upon or attached to the roof without prior written authorization from Bowman.
- h. If there is any failure by the Owner or lessee or other occupant or user to use reasonable care in maintaining the Roofing System.
- i. If Owner fails to comply with any term and/or condition stated in this 10-Year Water Tightness Limited Warranty.
- k. If water is allowed to cascade onto any part of the roofing system in a manner other than as originally installed.
- l. If leaks are due to ventilators, skylights, gutter, valleys, flashings, or penetrations of the roof associated with signs, vents, equipment, or other causes.

4. During the term of this Warranty, Bowman, its sales representatives and employees, shall have free access to the roof during regular business hours.

5. In the event that the roofing system is constructed in a manner which differs from the drawings submitted by Bowman, or if additional structures are placed in or around the roofing system by someone other than Bowman, Bowman shall not have any obligation under this 10-Year Water Tightness Limited Warranty until final drawings of the completed roof are submitted to Bowman and accepted in writing by Bowman. Such drawings must show the exact number,

size and location of all roof penetrations and roof-top equipment. Photos of the roof should accompany the drawings.

6. Bowman shall not have any obligation under this 10-Year Water Tightness Limited Warranty until all bills for installation, supplies and services due Bowman have been paid in full.

7. Bowman shall not be responsible for any consequential damages or loss to the building, its contents or other materials, unless Bowman has failed to promptly respond to a request for repairs and such damages could otherwise have been averted. If Bowman responds to a written request within three (3) working days after receipt of notification by Owner that there are leaks which Owner contends Bowman has the obligation to repair, such response shall be deemed to have been prompt.

8. Bowman's failure at any time to enforce any of the terms or conditions stated herein shall not be construed to be a waiver of such provision or of the right to exercise any right in the future.

9. This 10-Year Water Tightness Limited Warranty supersedes and is in lieu of any and all other warranties (whether express or implied) that are either in addition to or in conflict with the term(s) stated herein.

10. If the Roofing System is covered by products of more than one roofing products manufacturer, this 10-Year Water Tightness Limited Warranty applies only to those portions of such roof which are covered solely by Bowman's products.

11. Notwithstanding any other provision of this 10-Year Water Tightness Limited Warranty, Bowman shall not have any liability or responsibility at any time for, or as a consequence of, any condensation or underside corrosion which is nor was caused at any time in part or wholly by any condensation resulting from either or both of the following:

- a. The use of any inadequate vapor barrier where the insulation is installed immediately beneath the roof panels. An adequate vapor barrier is defined as one which has a perm rating of .05 or less with sealed joints and perimeter.
- b. Inadequate ventilation of the space between a roof panel and insulation, when insulation is installed directly on top of an existing roof.

This 10-Year Water Tightness Limited Warranty is tendered for the sole benefit of the original Owner as named below and is not transferable or assignable.

The laws of the State of Texas shall govern the rights and duties of the parties under this agreement, and jurisdiction and venue is fixed in HIDALGO County, Texas.

ISSUED this 21st day of August, 1995.

BOWMAN DISTRIBUTING COMPANY, INC.
a Texas Corporation


BY: Denis L. Bowman

ITS: President

(Title)

STATE OF TEXAS §
 §
COUNTY OF CAMERON §

This instrument was acknowledged before me on the 18th day of October, 1995
by DENNIS BOWMAN, PRESIDENT of Bowman
Distributing Company, Inc., a Texas corporation, on behalf of said corporation.



Jackie D. Morgan
NOTARY PUBLIC, STATE OF TEXAS

ACCEPTED:

OWNER
BY: _____
ITS: _____
 (Title)

STATE OF TEXAS §
 §
COUNTY OF _____ §

This instrument was acknowledged before me on the ____ day of _____, 1995
by _____ of _____
_____, a _____, on behalf of _____
_____.

NOTARY PUBLIC, STATE OF TEXAS



QUALITY ASSURANCE PROGRAM

10
Y
E
A
R
W
A
R
R
A
N
T
Y

Owner: Edinburg Community Independent School District
 Address: 921 East Schunior, Edinburg, TX 78539
 Warranty Number: 22136
 Building Description: Edinburg Middle School, Rogers and Doolittle Road, Edinburg, TX
 Roof Area: 84,000 sq. ft.
 Date of Completion: 8/01/95
 Roofing Contractor: Ric Roofing, Inc.
 Address: 1114 E Jefferson Road, P O Box 530103, Harlingen, TX 78553-0103
 System Type: NEW CONSTRUCTION: 2C60 MB
 Installation Contract Price: \$220,000.00

Tremco Incorporated hereby warrants to the above named Owner that, subject to the terms, conditions and limitations stated herein, it will repair any leaks in the above described Tremco Roofing System (hereinafter called TRS), as installed by the above named roofing contractor, for a period of ten (10) years from the date of completion (except as stated in Paragraph 9). TRS shall be defined as the weatherproofing assembly and its components as specified by Tremco which includes the following: membrane, insulation, flashings, and termination details.

- A. This warranty does not cover any damage or failure of the TRS or any part thereof as a result of:
1. Natural or accidental disasters, including but not limited to, damage caused by lightning, hurricanes, floods, hurricanes force winds (74 mph) or greater, tornadoes, earthquakes, fire, vandalism, animals, or penetration of the membrane or chemical attack by outside agents.
 2. Use of material not specified by Tremco.
 3. Any intentional or negligent act by the Owner or any third party, including but not limited to, misuse, traffic or storage of materials on roof.
 4. Disruption, extension or obstruction of any unapproved flashing or metal work, or faulty construction or design of building components, including parapet walls, coping, chimneys, skylights, vents or roof deck, or lack of proper, proper or adequate drainage resulting in ponding water on roof.
- B. In the event any leaks should occur in the TRS roof within the warranty period, the Owner, or named above, shall notify Tremco Incorporated, 10001 Dublin Boulevard, Cleveland, OH 44104, in writing or telephone (however in no event more than thirty (30) days after leakage is or should have been discovered. Tremco will inspect the TRS roof and if the leak is within coverage of this warranty, will, at its own expense make or cause to be made all necessary repairs to the TRS roof to put it in watertight condition. To the extent any repairs to any part of the building other than the TRS roof are required, or the removal or replacement of any traffic surfaces or other accessories built over the roof are required in order to put the TRS roof in watertight condition, the liability or expense for such repair, removal or replacement shall be assumed and paid by the Owner. If the leak is not within warranty coverage, Tremco shall advise the Owner, and the Owner shall have the repairs performed within thirty (30) days, according to Tremco specifications, by a Tremco approved applicator. In the event an emergency condition exists which requires immediate repair to avoid substantial damage to the building or its contents, Tremco may instruct the Owner to make necessary temporary repairs.
- C. Tremco, at its option, may upon reasonable notice, void this warranty for any of the following reasons:
1. Building settlement, excessive cracking or failure of the roof deck, coping and parapet walls and/or infiltration or deterioration of structure in, through or around walls, coping, underlying structure, hardware or attachment.
 2. Change in usage of building without prior written approval of Tremco, repairs or alterations of roof or installation of structures, fixtures or utilities on or through roof without prior approval of Tremco.
 3. Failure of Owner to pay all bills for installation, supplies and services sold in connection with this project, failure to notify Tremco within prescribed time of discovery of defect and/or leak, failure to repair non warranty leaks within time specified, according to Tremco specification, by approved applicator.
 4. Failure of Owner to comply with roof maintenance as outlined in the Owners Manual.
- D. THIS WARRANTY IS GIVEN IN LIEU OF ANY AND ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. THE REMEDIES IN PARAGRAPH B. ABOVE, ARE THE SOLE AND EXCLUSIVE REMEDIES OF THE OWNER FOR ANY AND ALL CLAIMS ARISING IN TORT OR BY CONTRACT WITH OR WITHOUT REGARD TO THE TRS. NO REPRESENTATIVE HAS AUTHORITY TO VARY OR ALTER THESE TERMS. IN NO EVENT SHALL TREMCO BE LIABLE FOR ANY DAMAGE TO THE BUILDING ITSELF (OTHER THAN THE TRS), THE CONTENTS OF THE BUILDING, OR ANY OTHER SPECIAL, INCIDENTAL OR CONSEQUENTIAL DAMAGES. TREMCO'S TOTAL LIABILITY SHALL BE THE FIRST YEAR OF THIS WARRANTY'S TERM IN ANY EVENT EXCEPT IN THE CASES WHERE THE DAMAGE TO THE TRS IS CAUSED BY A DEFECT IN THE TREMCO ROOFING SYSTEM AS APPEARS ABOVE. TREMCO'S MAXIMUM LIABILITY, FOLLOWING YEAR ONE, SHALL BE PRORATED AS A STRAIGHT LINE DECLINING VALUE BASED OVER THE LIFE OF THE WARRANTY, AND SHALL NOT IN ANY EVENT EXCEED SUCH PRORATED AMOUNT. TREMCO SHALL NOT BE LIABLE FOR ANY DAMAGES WHICH ARE BASED UPON CONTRACTIBLE, SPECIAL OR WARRANTY, STRICT LIABILITY OR ANY OTHER THEORY OF LIABILITY OTHER THAN THE EXCLUSIVE LIABILITY SET FORTH IN THIS WARRANTY.
- E. Tremco's liability under this warranty shall not become effective until all bills for installation, supplies and services sold in connection with the roof have been paid in full.
- F. The warranty period shall commence from the date of completion. Any delay in the effective date of this warranty due to circumstances referenced in Paragraph E shall not extend the original warranty expiration date.
- G. Quality Assurance: Tremco will, during the annual, and fifth year of this warranty, inspect and provide a written Report for Summary of the roof.
- H. During the period of this warranty, Tremco will have free access to the roof and related premises during regular business hours, and will retain the right to make safe operations and properly repair such operations.
- I. The Owner's rights under this warranty are not transferable.


Signed the 7th day of November 19 95
 TREMCO INCORPORATED
 By [Signature]
 The Warranty Administrator

**ROOF WARRANTY INFORMATION
EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT**


August 20, 2007

Tremco Warranty Number	Project Name	Contractor	Warranty Length (Years)	Warranty Effective Date	Project Size (S. F.)
101709	New High School 2600 E. Wisconsin Edinburg, TX	Rain King, Inc.	20	08/20/2004	303,800
89539	South Middle School 601 W. Freddy Gonzalez Edinburg, TX	American Contracting U. S. A., Inc.	15	04/12/2002	172,700
82741	Lyndon B. Johnson Elem. School 1801 E Sprague Edinburg, TX	American Contracting U. S. A., Inc.	15	10/11/2000	42,500
76447	Villarreal Elementary School 2-1/2 Mi. E. 281 on Monte Cristo Rd. Edinburg, TX	Rio Roofing , Inc.	15	12/15/1999	8,800
78097	Freddy Gonzalez Elementary School 2401 Sugar Road Edinburg, TX	American Contracting U. S. A., Inc.	15	09/03/1999	44,600
27080	Harwell Middle School 1100 E. Ebony Lane Edinburg, TX	American Contracting U. S. A., Inc.	15	08/28/1997	164,000
25514	Edinburg High School 801 E. Canton Rd. Edinburg, TX	American Contracting U. S. A., Inc.	15	12/19/1996	210,000
25509	Lincoln Elementary School 1319 E. Lovett St. Edinburg, TX	American Contracting U. S. A., Inc.	15	12/19/1996	55,000
25513	Travis Elementary School 1200 South 21 st Street Edinburg, TX	American Contracting U. S. A., Inc.	15	12/19/1996	60,000
24739	Kennedy Elementary School Raul Longoria Rd. San Carlos, TX	Rio Roofing , Inc.	10	11/05/1996 Expired	9,400

Tremco Warranty Number	Project Name	Contractor	Warranty Length (Years)	Warranty Effective Date	Project Size (S. F.)
24740	Cano-Gonzalez Elementary School Raul Longoria Rd. Edinburg, TX	Rio Roofing , Inc.	10	11/05/1996 Expired	9,400
24740	Lamar Elementary School Freddy Gonzalez Rd. Edinburg, TX	Rio Roofing , Inc.	10	11/05/1996 Expired	9,400
24657	Eisenhower Elementary School 2901 Russell Rd. Edinburg, TX	Halco Roofing of Texas, Inc.	10	01/13/1996 Expired	10,100
	Edinburg Memorial Junior High Edinburg, TX		10	08/08/1995 Expired	84,000
	Rogers Road Elementary School Edinburg, TX		10	07/27/1994 Expired	7,200
	Canterberry Elementary School Phase 2 Edinburg, TX		10	06/19/1994 Expired	2,100
	Canterberry Elementary School Edinburg, TX		10	02/16/1993 Expired	11,700



MEMORIAL MIDDLE SCHOOL
SITE PLAN
EDINBURG C.I.S.D.
EDINBURG C.I.S.D.



MEMORIAL MIDDLE SCHOOL
EDINBURG C.I.S.D.
GROUND LEVEL FLOOR PLAN



PLM Summary Report

NVLAP Lab Code 102056-0
TDSHS License No. 30-0084

2051 Valley View Lane
Farmers Branch, TX 75234 Phone: (972) 241-8460

Client :	Terracon - Pharr	Lab Job No. :	22B-02539
Project :	Memorial Middle School	Report Date :	03/09/2022
Project # :	88227050	Sample Date :	03/06/2022
Identification :	Asbestos, Bulk Sample Analysis		
Test Method :	Polarized Light Microscopy / Dispersion Staining (PLM/DS) EPA Method 600 / R-93 / 116		

On 3/8/2022, thirty nine (39) bulk material samples were submitted by Eloy Palacios of Terracon - Pharr for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
1	Pipe Insulation Mastic (White), Mechanical Room 112, Section B	None Detected - Thermal Insulation None Detected - Foil Wrap None Detected - White Mastic
2	Pipe Insulation Mastic (White), Mechanical Room 4, Section D	None Detected - White Mastic
3	Pipe Insulation Mastic (White), 2nd Floor, Mechanical Room 8, Section A	None Detected - Thermal Insulation None Detected - Foil Wrap None Detected - White Mastic
4	Pipe Insulation Mastic (White), Mechanical Room 112, Section B	None Detected - Thermal Insulation None Detected - White Mastic
5	Pipe Insulation Mastic (White), Mechanical Room 4, Section D	None Detected - Thermal Insulation None Detected - White Mastic
6	Pipe Insulation Mastic (White), 2nd Floor, Mechanical Room 8, Section H	None Detected - Thermal Insulation None Detected - White Mastic
7	HVAC Duct Mastic (Gray), Mechanical Room 112, Section B	None Detected - Paper / Foil Wrap None Detected - Gray Mastic
8	HVAC Duct Mastic (Gray), Mechanical Room 4, Section D	None Detected - Paper / Foil Wrap None Detected - Gray Mastic
9	HVAC Duct Mastic (Gray), 2nd Floor, Mechanical Room 8, Section A	None Detected - Gray Mastic
10	Drywall Construction (White) with Texture (Light), Mechanical Room 112, Section B	None Detected - Drywall Material None Detected - Joint Compound None Detected - Texture
11	Drywall Construction (White) with Texture (Light), Mechanical Room 4, Section D SEC	None Detected - Drywall Material None Detected - Joint Compound None Detected - Texture
12	Drywall Construction (White) with Texture (Light), 2nd Floor, Room 216, SEC	None Detected - Drywall Material None Detected - Texture / Joint Cmpd



PLM Summary Report

NVLAP Lab Code 102056-0
TDSHS License No. 30-0084

2051 Valley View Lane
Farmers Branch, TX 75234 Phone: (972) 241-8460

Client :	Terracon - Pharr	Lab Job No. :	22B-02539
Project :	Memorial Middle School	Report Date :	03/09/2022
Project # :	88227050	Sample Date :	03/06/2022
Identification :	Asbestos, Bulk Sample Analysis		
Test Method :	Polarized Light Microscopy / Dispersion Staining (PLM/DS) EPA Method 600 / R-93 / 116		

On 3/8/2022, thirty nine (39) bulk material samples were submitted by Eloy Palacios of Terracon - Pharr for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
13	Drywall Construction (White) with Texture (Light), 1st Floor, Mechanical Room 2, SEC	None Detected - Joint Compound None Detected - Texture
14	Drywall Construction (White) with Texture (Light), Storage Room, Floor 1, NEC	None Detected - Drywall Material None Detected - Joint Compound None Detected - Texture
15	Drywall Construction (White) with Texture (Light), Mechanical Room 8, Floor 1, SEC	None Detected - Drywall Material None Detected - Joint Compound None Detected - Texture
16	Drywall Construction (White) with Texture (Light), Room 222, Floor 2, NWC	None Detected - Drywall Material None Detected - Texture / Joint Cmpd
17	CMU Texture, Mechanical Room 112, Section B	None Detected - Paint / Texture
18	CMU Texture, Mechanical Room 4, Section D, SWC	None Detected - Paint / Texture
19	CMU Texture, 2nd Floor, Mechanical Room 8, Section A	None Detected - Paint / Texture
20	CMU Texture, 2nd Floor, Mechanical Room 2, East Wall	None Detected - Paint / Texture
21	CMU Texture, 1st Floor, Storage Room, NEC	None Detected - Paint / Texture
22	CMU Texture, 1st Floor, Mechanical Room 3, NWC	None Detected - Paint / Texture
23	CMU Texture, 2nd Floor, Room 222, NWC	None Detected - Paint / Texture
24	2 x 4 Suspended Acoustic Ceiling Tile (White with Pinholes and Fissures), Academic Building, Room 216, SWC	None Detected - Acoustic Tile
25	2 x 4 Suspended Acoustic Ceiling Tile (White with Pinholes and Fissures), Fine Arts Building, Main Hallway	None Detected - Acoustic Tile
26	2 x 4 Suspended Acoustic Ceiling Tile (White with Pinholes and Fissures), Cafeteria SWC	None Detected - Acoustic Tile
27	Pipe Insulation Mastic (White), Mechanical Room North, Fine Arts Building	None Detected - Thermal Insulation None Detected - White Mastic
28	Pipe Insulation Mastic (White), Mechanical Room North, Fine Arts Building	None Detected - Thermal Insulation None Detected - White Mastic



PLM Summary Report

NVLAP Lab Code 102056-0
TDSHS License No. 30-0084

2051 Valley View Lane
Farmers Branch, TX 75234 Phone: (972) 241-8460

Client :	Terracon - Pharr	Lab Job No. :	22B-02539
Project :	Memorial Middle School	Report Date :	03/09/2022
Project # :	88227050	Sample Date :	03/06/2022
Identification :	Asbestos, Bulk Sample Analysis		
Test Method :	Polarized Light Microscopy / Dispersion Staining (PLM/DS) EPA Method 600 / R-93 / 116		


On 3/8/2022, thirty nine (39) bulk material samples were submitted by Eloy Palacios of Terracon - Pharr for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:


Sample Number	Client Sample Description / Location	Asbestos Content
29	Pipe Insulation Mastic (White), Mechanical Room South, Fine Arts Building	None Detected - Thermal Insulation None Detected - White Mastic
30	Pipe Insulation Mastic (White), Mechanical Room North, Fine Arts Building	None Detected - Thermal Insulation None Detected - White Mastic
31	Pipe Insulation Mastic (White), Mechanical Room North, Fine Arts	None Detected - Thermal Insulation None Detected - White Mastic
32	Pipe Insulation Mastic (White), Mechanical Room South, Fine Arts	None Detected - Thermal Insulation None Detected - White Mastic
33	CMU Texture, Mechanical Room North, Fine Arts	None Detected - Paint / Texture
34	CMU Texture, Mechanical Room South, Fine Arts	None Detected - Paint / Texture
35	CMU Texture, Cafeteria, NEC	None Detected - Paint / Texture
36	CMU Texture, Cafeteria, SEC	None Detected - Paint / Texture
37	CMU Texture, Cafeteria, NWC	None Detected - Paint / Texture
38	CMU Texture, Cafeteria, SWC	None Detected - Paint / Texture
39	CMU Texture, Kitchen, SEC	None Detected - Paint / Texture

These samples were analyzed by layers. Quantification, unless otherwise noted, is performed by calibrated visual estimate. The test report shall not be reproduced except in full without written approval of the laboratory. The results relate only to the items tested. These test results do not imply endorsement by NVLAP or any agency of the U.S. Government. Accredited by the National Voluntary Laboratory Accreditation Program for Bulk Asbestos Fiber Analysis under Lab Code 102056-0.



Analyst(s): Bruce Crabb
Lab Manager : Heather Lopez
Lab Director : Bruce Crabb

Approved Signatory : 

Approved Signatory : 

Thank you for choosing Moody Labs

This Page Left Intentionally Blank

Moody Labs
 2051 Valley View Lane
 Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
 Supplement to PLM Summary Report

NVLAP Lab Code 102056-0
 TDSHS License No. 30-0084

Client : Terracon - Pharr
 Project : Memorial Middle School
 Project # : 88227050

Lab Job No. : 22B-02539
 Report Date : 03/09/2022

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
1	Thermal Insulation (Yellow)	3%	Mineral Wool Fibers	95%	03/08	BC
			Resin Binders	5%		
	Foil Wrap (Silver)	2%	Metal Foil	100%		
	White Mastic (Off-White)	95%	Quartz Grains	5%		
			Pigment / Binders	95%		
2	White Mastic (Off-White)	100%	Quartz Grains	5%	03/08	BC
			Pigment / Binders	95%		
3	Thermal Insulation (Yellow)	3%	Mineral Wool Fibers	95%	03/08	BC
			Resin Binders	5%		
	Foil Wrap (Silver)	2%	Metal Foil	100%		
	White Mastic (Off-White)	95%	Quartz Grains	5%		
			Pigment / Binders	95%		
4	Thermal Insulation (Yellow)	5%	Mineral Wool Fibers	95%	03/08	BC
			Resin Binders	5%		
	White Mastic (Off-White)	95%	Quartz Grains	5%		
			Pigment / Binders	95%		
5	Thermal Insulation (Yellow)	5%	Mineral Wool Fibers	95%	03/08	BC
			Resin Binders	5%		
	White Mastic (Off-White)	95%	Quartz Grains	5%		
			Pigment / Binders	95%		
6	Thermal Insulation (Yellow)	5%	Mineral Wool Fibers	95%	03/08	BC
			Resin Binders	5%		
	White Mastic (Off-White)	95%	Quartz Grains	5%		
			Pigment / Binders	95%		
7	Paper / Foil Wrap (Tan / Silver)	15%	Cellulose Fibers	60%	03/08	BC
			Glass Wool Fibers	20%		
			Metal Foil	20%		
	Gray Mastic (Gray)	85%	Glass Wool Fibers	1%		
			Graphite	10%		
			Calcite Binders / Fillers	89%		

Moody Labs
 2051 Valley View Lane
 Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0
 TDSHS License No. 30-0084

Client : Terracon - Pharr
 Project : Memorial Middle School
 Project # : 88227050

Lab Job No. : 22B-02539
 Report Date : 03/09/2022

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
8	Paper / Foil Wrap (Tan / Silver)	15%	Cellulose Fibers	60%	03/08	BC
			Glass Wool Fibers	20%		
	Gray Mastic (Gray)	85%	Metal Foil	20%		
			Glass Wool Fibers	1%		
			Graphite	10%		
			Calcite Binders / Fillers	89%		
9	Gray Mastic (Gray)	100%	Glass Wool Fibers	1%	03/08	BC
			Calcite Binders / Fillers	99%		
10	Drywall Material (White)	15%	Glass Wool Fibers	2%	03/08	BC
			Cellulose Fibers	1%		
			Gypsum / Binders	97%		
	DW Paper / Tape (Tan / White)	15%	Cellulose Fibers	100%		
	Joint Compound (White)	25%	Calcite / Talc / Binders	100%		
Texture (White)	45%	Calcite / Talc / Binders	100%			
11	Drywall Material (White)	45%	Glass Wool Fibers	2%	03/08	BC
			Cellulose Fibers	1%		
			Gypsum / Binders	97%		
	DW Paper / Tape (Tan / White)	15%	Cellulose Fibers	100%		
	Joint Compound (White)	15%	Calcite / Talc / Binders	100%		
Texture (White)	25%	Calcite / Talc / Binders	100%			
12	Drywall Material (White)	55%	Glass Wool Fibers	2%	03/08	BC
			Cellulose Fibers	1%		
			Gypsum / Binders	97%		
	DW Paper Facing (Tan)	15%	Cellulose Fibers	100%		
Texture / Joint Cmpd (White)	30%	Calcite / Talc / Binders	100%			
13	Joint Compound (White)	55%	Calcite / Talc / Binders	100%	03/08	BC
	DW Tape (White)	10%	Cellulose Fibers	100%		
	Texture (White)	35%	Calcite / Talc / Binders	100%		

Moody Labs
 2051 Valley View Lane
 Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0
 TDSHS License No. 30-0084

Client : Terracon - Pharr
 Project : Memorial Middle School
 Project # : 88227050

Lab Job No. : 22B-02539
 Report Date : 03/09/2022

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
14	Drywall Material (White)	65%	Glass Wool Fibers	2%	03/08	BC
			Cellulose Fibers	1%		
			Gypsum / Binders	97%		
	DW Paper / Tape (Tan / White)	10%	Cellulose Fibers	100%		
15	Joint Compound (White)	10%	Calcite / Talc / Binders	100%	03/08	BC
	Texture (White)	15%	Calcite / Talc / Binders	100%		
	Drywall Material (White)	45%	Glass Wool Fibers	2%		
			Cellulose Fibers	1%		
		Gypsum / Binders	97%	03/08	BC	
DW Paper / Tape (Tan / White)	15%	Cellulose Fibers	100%			
Joint Compound (White)	15%	Calcite / Talc / Binders	100%			
Texture (White)	25%	Calcite / Talc / Binders	100%			
16	Drywall Material (White)	65%	Glass Wool Fibers	2%	03/08	BC
			Cellulose Fibers	1%		
			Gypsum / Binders	97%		
	DW Paper Facing (Tan)	15%	Cellulose Fibers	100%		
17	Texture / Joint Cmpd (White)	20%	Calcite / Talc / Binders	100%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		
18			Pigment / Binders	75%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		
19			Pigment / Binders	75%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		
20			Pigment / Binders	75%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		
21			Pigment / Binders	75%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		
22			Pigment / Binders	75%	03/09	BC
	Paint / Texture (White)	100%	Calcite	25%		

Moody Labs
 2051 Valley View Lane
 Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
 Supplement to PLM Summary Report

NVLAP Lab Code 102056-0
 TDSHS License No. 30-0084

Client : Terracon - Pharr
 Project : Memorial Middle School
 Project # : 88227050

Lab Job No. : 22B-02539
 Report Date : 03/09/2022

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
23	Paint / Texture (White)	100%	Calcite	25%	03/09	BC
			Pigment / Binders	75%		
24	Acoustic Tile (Light Tan)	100%	Cellulose Fibers	40%	03/09	BC
			Mineral Wool Fibers	40%		
			Perlite	20%		
25	Acoustic Tile (Light Tan)	100%	Cellulose Fibers	40%	03/09	BC
			Mineral Wool Fibers	40%		
			Perlite	20%		
26	Acoustic Tile (Light Tan)	100%	Cellulose Fibers	40%	03/09	BC
			Mineral Wool Fibers	40%		
			Perlite	20%		
27	Thermal Insulation (Yellow)	15%	Mineral Wool Fibers	95%	03/09	BC
			Resin Binders	5%		
	White Mastic (Off-White)	85%	Quartz Grains	2%		
			Pigment / Binders	98%		
28	Thermal Insulation (Yellow)	15%	Mineral Wool Fibers	95%	03/09	BC
			Resin Binders	5%		
	White Mastic (Off-White)	85%	Quartz Grains	2%		
			Pigment / Binders	98%		
29	Thermal Insulation (Yellow)	15%	Mineral Wool Fibers	95%	03/09	BC
			Resin Binders	5%		
	White Mastic (Off-White)	85%	Quartz Grains	2%		
			Pigment / Binders	98%		
30	Thermal Insulation (Yellow)	5%	Mineral Wool Fibers	95%	03/09	BC
			Resin Binders	5%		
	White Mastic (White)	95%	Wollastonite	3%		
			Glass Wool Mesh	3%		
			Binders / Fillers	94%		

Moody Labs
 2051 Valley View Lane
 Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
 Supplement to PLM Summary Report

NVLAP Lab Code 102056-0
 TDSHS License No. 30-0084

Client : Terracon - Pharr
 Project : Memorial Middle School
 Project # : 88227050

Lab Job No. : 22B-02539
 Report Date : 03/09/2022

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst		
31	Thermal Insulation (Yellow)	5%	Mineral Wool Fibers	95%	03/09	BC		
	White Mastic (Off-White)	95%	Resin Binders	5%				
32	Thermal Insulation (Yellow)	5%	Quartz Grains	2%	03/09	BC		
			Pigment / Binders	98%				
			White Mastic (White)	95%			Wollastonite	3%
			Binders / Fillers	97%				
33	Paint / Texture (White)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
34	Paint / Texture (White)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
35	Paint / Texture (Blue/White)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
36	Paint / Texture (Green/White)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
37	Paint / Texture (White/Green)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
38	Paint / Texture (White/Blue)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				
39	Paint / Texture (White/Orange)	100%	Calcite	25%	03/09	BC		
			Pigment / Binders	75%				



SERVICE | QUALITY | INTEGRITY | SUSTAINABILITY

200 South 10th Street
Suite 901
McAllen, TX 78501
v 956.683.1640

Addendum

DATE

4/7/2022

ADDENDUM NO.

2

PROJECT

218007.002 | Edinburg CISD - Memorial MS - HVAC Improvements



The work described herein shall be added to the scope of work defined by the contract documents or it shall modify the scope of work defined by the contract documents as described. This work shall become a part of the contract documents by addendum.

SPECIFICATIONS

Item 01 Specification 23 73 13 – Modular Central Station Air Handling Units

- A. Replace specification section in its entirety.

DRAWINGS

Item 02 SHEET M0.01 – MECHANICAL LEGEND

- A. Added general note 23.

Item 03 SHEET MD2.12F – LEVEL 1 MECHANICAL DEMO PLAN – F.

- A. Revised keyed notes 2 and 3.

Item 04 SHEET MD2.13G – LEVEL 1 MECHANICAL DEMO PLAN – G.

- A. Replaced keyed note 4 with keyed note 3 for EXRTU-19 and EXRTU-20.

Item 05 SHEET MD3.12 – ENLARGED MECHANICAL DEMO PLAN

- A. Revised keyed notes 3 and 10.

Item 06 SHEET MD3.13 – ENLARGED MECHANICAL DEMO PLAN

- A. Scheduled cooling tower 3-way valve to be demolished.
- B. Clarified that the chillers and cooling towers to remain.
- C. Revised keyed note 6.

Item 07 SHEET M1.11 – COMPOSITE LEVEL 1 MECHANICAL HYDRONIC PIPING PLAN

- A. Added differential pressure sensor.

Item 08 SHEET M2.11A – LEVEL 1 MECHANICAL PLAN - A

Addendum No. 1

A. Revised keyed note 1.

Item 09 SHEET M2.11B – LEVEL 1 MECHANICAL PLAN - B

A. Revised keyed note 1.

Item 10 SHEET M2.11C – LEVEL 1 MECHANICAL PLAN - C

A. Revised keyed note 1.

Item 11 SHEET M2.11D – LEVEL 1 MECHANICAL PLAN - D

A. Revised keyed note 1.

Item 12 SHEET M3.10 – ENLARGED MECHANICAL ROOM PLANS

A. Revised view of enlarged mechanical room plan #5.

Item 13 SHEET M3.11 – ENLARGED MECHANICAL ROOM PLANS

- A. Replaced keyed note 5 with keyed note 10 on LEVEL 2A MECHANICAL AHU-8.
- B. Revised view of LEVEL 2B MECHANICAL AHU-9.
- C. Revised view of LEVEL 2B MECHANICAL AHU-10.

Item 14 SHEET M3.13 – ENLARGED MECHANICAL ROOM PLANS

- A. Corrected title block.
- B. Added control valves to condenser water at chillers.
- C. Revised keyed note 9.

Item 15 SHEET M4.02 – MECHANICAL CONTROLS

- A. Revised Single Zone VAV Air Handling Unit – Control Schematic and Sequence of Operations.
- B. Revised Multi Zone VAV Air Handling Unit – Control Schematic and Sequence of Operations.

Item 16 SHEET M4.03 – MECHANICAL CONTROLS

- A. Revised Chilled Water System – Variable Primary Flow – Control Schematic Sequence of Operations
- B. Revised Condenser Water System – Chiller Plant – Control Schematic and Sequence of Operations

Item 17 SHEET M5.01 – MECHANICAL SCHEDULES

- A. Revised fan schedule.
- B. Revised packaged dx roof top unit schedule

Item 18 SHEET M5.02 – MECHANICAL SCHEDULES

- A. Removed duplicate details #7 and #8.

Item 19 SHEET M6.01 – MECHANICAL SCHEDULES

- A. Corrected detail numbering.

Item 20 SHEET EP2.11C – LEVEL 1 ELECTRICAL POWER PLAN - C

Addendum No. 1

- A. Added distribution panel DP-C.

Item 21 SHEET EP2.12G – LEVEL 1 ELECTRICAL POWER PLAN - G

- A. Showed location of existing panel CK.

Item 22 SHEET E3.01 – ELECTRICAL ENLARGED POWER PLANS

- A. Added power for Refrigerant Monitoring Panel and chiller valves.

Item 23 SHEET E4.01 – ELECTRICAL ONE-LINE DIAGRAM

- A. Added distribution panel DP-C.
- B. Revised the feeding of branch circuit panels MC1, MC2, MD1, MD2, MF1 and MG1.

Item 24 SHEET E5.01 – ELECTRICAL SHCEDULES

- A. Revised the parameters of panels MC1 and MD1.

Item 25 SHEET E5.02 – ELECTRICAL SHCEDULES

- A. Revised the parameters of panel MG1.

Item 26 CSP Request for Information

- A. Question: Schedule/Phasing: Is there a project schedule or phasing plan for Memorial Middle School and or Edinburg High School?
Answer: There is no set schedule nor phasing for the project. This will be determined once the project is awarded. The owner has expressed the desire to replace one air handler at a time to allow for relocation of students as staff during the down time of the equipment. During long periods of time where there is no school, such as holidays, the contractor may schedule several equipment replacements.
- B. Question: Schedule/Phasing: Is there a project completion deadline for Memorial Middle School and or Edinburg High School to meet the funding requirements of the ESSER funds?
Answer: There is an expected date of completion of 2024.

END OF ADDENDUM

SECTION 23 73 13

MODULAR INDOOR CENTRAL STATION AIR HANDLING UNITS

PART 1 - GENERAL

1.1 WORK INCLUDED

- A. Indoor central station air handling unit.
- B. The Contractor and the building automation controls installer shall participate in the commissioning process of this equipment as required; including, but not limited to, meeting attendance, completion of checklists, and participation in functional testing.

1.2 RELATED SECTIONS

- A. Section 23 02 00 - Basic Materials and Methods for HVAC
- B. Section 23 05 16 - Expansion Fittings and Loops for HVAC Piping
- C. Section 23 05 13 - Common Motor Requirements for HVAC Equipment
- D. Section 23 05 26 - Variable Frequency Motor Speed Control for HVAC Equipment
- E. Section 23 05 48 - Vibration and Seismic Controls for HVAC Piping and Equipment
- F. Section 23 07 13 - Duct Insulation
- G. Section 23 31 13 - Metal Ductwork
- H. Section 23 33 00 - Ductwork Accessories
- I. Section 23 34 00 - HVAC Fans
- J. Section 23 41 00 - Air Filters

1.3 REFERENCES

- A. AHRI 260 - Sound Rating of Ducted Air Moving and Conditioning Equipment.
- B. AHRI 410 - Forced-Circulation Air-Cooling and Air-Heating Coils.
- C. AHRI 430 (I-P) - Performance Rating of Central Station Air-handling Unit Supply Fans.
- D. AMCA 210 - Laboratory Methods of Testing Fans for Certified Aerodynamic Performance Rating.
- E. AMCA 300 - Reverberant Room Method for Sound Testing of Fans.
- F. ASHRAE Std 111 - Measurement, Testing, Adjusting, and Balancing of Building HVAC Systems.
- G. ASHRAE Std 15 - Safety Standard for Refrigeration Systems.
- H. ASHRAE Std 62.1 - Ventilation for Acceptable Indoor Air Quality.
- I. ASHRAE Std 90.1 I-P - Energy Standard for Buildings Except Low-Rise Residential Buildings.
- J. ICC (IECC) - International Energy Conservation Code.

- K. NEMA MG 1 - Motors and Generators.
- L. NFPA 70 - National Electrical Code.
- M. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems.

1.4 QUALITY ASSURANCE

- A. Unit performance shall be certified in accordance with AHRI 430 (I-P) for central station air handling units.
- B. Coil performance shall be certified in accordance with AHRI 410.
- C. Direct-expansion coils shall be designed and tested in accordance with ASHRAE Std 15 Safety Code for Mechanical Refrigeration.
- D. Insulation and insulation adhesive shall comply with NFPA 90A requirements or flame spread and smoke generation.
- E. Unit shall be rated for sound performance in accordance with AHRI 260 and AMCA 300.
- F. Unit shall be provided to comply with the maximum allowable fan horsepower per ICC (IECC) and ASHRAE Std 90.1 I-P.

1.5 GENERAL DESCRIPTION

- A. Indoor mounted, central station air handling unit designed to provide air to a conditioned space as required to meet specified performance requirements for ventilation, heating, cooling, filtration, and distribution. Unit shall be assembled for horizontal/vertical application and arranged to discharge conditioned air as shown on the drawings. Units shall be supplied by the specified manufacturer.

1.6 SUBMITTALS

- A. Submit shop drawings and product data under provisions of Division One.
- B. Shop drawings shall indicate assembly, unit dimensions, weight loading, required clearances, construction details, and field connection details.
- C. Product data shall indicate dimensions, weights, capacities, ratings, fan performance, motor electrical characteristics, and gauges and finishes of materials.
- D. Provide fan curves with specified operating point clearly plotted.
- E. Submit product data of filter media, filter performance data, filter assembly, and filter frames.
- F. Submit electrical requirements for power supply wiring including wiring diagrams for interlock and control wiring, clearly indicating factory installed and field installed wiring.
- G. Submit manufacturer's installation instructions under provisions of Division One.
- H. Submit operation and maintenance data under provisions of Section 23 02 00.
- I. Include instructions for lubrication, filter replacement, motor and drive replacement, spare parts lists, and wiring diagrams.

1.7 WARRANTY

- A. The air handling unit manufacturer shall warrant parts and labor for a period of eighteen (18) months from date of shipment, or twelve (12) months from date of start-up, whichever occurs first.

1.8 DELIVERY, STORAGE AND HANDLING

- A. Unit shall be stored and handled in accordance with the unit manufacturer's instructions.

1.9 ENVIRONMENTAL REQUIREMENTS

- A. Do not operate units for any purpose, temporary or permanent, until ductwork is clean, filters are in place, and fan has been test-run under observation.

1.10 OPERATIONS PERSONNEL TRAINING

- A. Provide a training session for the owner's operations personnel. Training session shall be performed by a qualified person who is knowledgeable in the subject system/equipment. Submit a training agenda two (2) weeks prior to the proposed training session for review and approval. Training session shall include at the minimum:
 - 1. Purpose of equipment.
 - 2. Principle of how the equipment works.
 - 3. Important parts and assemblies.
 - 4. How the equipment achieves its purpose and necessary operating conditions.
 - 5. Most likely failure modes, causes and corrections.
 - 6. On site demonstration.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

- A. Carrier
- B. Trane
- C. JCI
- D. Daikin
- E. Temtrol

2.2 GENERAL DESCRIPTION

- A. Unit shall be factory supplied, central station air handler suitable for the capacities and configurations as shown on drawings. Unit may consist of a fan and coil section with a factory installed chilled water or direct-expansion coil, heating coil section, electric heat section, face and bypass section, filter section, access section, mixing box or combination filter-mixing box, return fan, diffuser, or air blender as indicated on the drawings.
- B. All sections, whether assembled into a unit or supplied as separate components, shall have mating flanges for bolted assembly. The flange shall extend around the complete perimeter of each section. The manufacturer shall supply bolts and sufficient closed cell gasket for full perimeter coverage.

2.3 CASING

- A. All unit sections shall be supplied with a formed galvanized steel perimeter base rail of at least 6 inches in height designed to support the weight and structural integrity of the unit. Condensate drain connection will not penetrate the base rail. If external isolators are not used, provide 6 inch minimum

height housekeeping pads or sufficient overall height to provide p-trap with 1 inch greater than unit total static pressure.

- B. Unit panels for all sections shall be double wall construction. Panel deflection shall not exceed L/240 ratio at +5/-6 in w.c. of pressure at the panel midpoint. Casing panels shall be fully removable for easy access to the unit, and shall be secured to structural frame with aluminized or cadmium plated screws. Removal of panels must not affect the structural integrity of the unit. All panels shall have a minimum of 2-inch thick foam insulation (R-13). All panels shall be completely gasketed prior to shipping.
- C. Casing air leakage shall not exceed 0.5 CFM per square foot of casing surface area at +5/-6" in w.c. of pressure. Specified air leakage shall be accomplished without the use of caulk.
- D. Double wall hinged removable access doors with multiple handles shall be provided in the fan, coil, and filter sections on the drive side of the unit. Access doors must also be provided in all sections where the removal of sheet metal screws is required for unit access. Doors shall be of the same thickness and construction as the wall panels. A gasket shall be provided around the entire door perimeter. Access sections shall be installed where indicated on the drawings and shall be double walled hinged door.

2.4 FANS

- A. Units shall be provided with direct-driven, single-width, single-inlet (SWSI) airfoil plenum fans constructed per AMCA requirements for the duty specified. Class I fans are not acceptable. Fan wheels shall be aluminum construction and rated in accordance with and certified by AMCA 210. All fans shall be selected to deliver the specified airflow quantity at the specified operating Total Static Pressure and specified fan/motor speed. The fan shall be selected to operate at a system Total Static Pressure that does not exceed 90% of the specified fan's peak static pressure producing capability at the specified fan/motor speed. Each fan/motor assembly shall include a minimum 14 gauge spun steel fan inlet funnel, and a G90 galvanized steel motor support plate and fan base with 2" spring type vibration isolation. Provide horizontal spring type thrust restraints between the unit casing and each fan/motor assembly.
- B. Units delivering supply airflow rates of significant magnitude shall be equipped with multiple supply fans in an array configuration. Refer to scheduled values to verify motor quantity per unit. Where multiple fans are provided, provide a manual blank-off plate for each unit to be mounted upstream of each fan for isolation. Each unit shall have factory mounted conduit and wiring from each fan motor terminated at an external junction box.

2.5 MOTORS

- A. All motors shall be premium efficiency, totally enclosed fan-cooled (TEFC), selected at the specified operating voltage, RPM, and efficiency as specified or as scheduled elsewhere. Motors shall meet the requirements of NEMA MG 1 Part 30 and 31, section 4.4.2. Motor HP shall not exceed the scheduled HP as indicated in the AHU equipment schedules.
- B. All fan motors shall be operated from variable frequency drives. Variable frequency drives shall be furnished, installed, and wired by the installing Contractor. Reference Section 23 05 26 - Variable Frequency Motor Speed Control for HVAC Equipment for additional VFD requirements.
- C. All motors operated by variable frequency drive shall be equipped with a maintenance free, conductive microfiber, shaft grounding ring with a minimum of two rows of circumferential microfibers to discharge electrical shaft currents within the motor and/or its bearings.

2.6 COILS

- A. All coils shall be tested at 300 psig air pressure, under water.
- B. All coils shall be installed on tracks for easy removal from the air handling unit. Units that require disassembly of the unit for coil removal are not acceptable.

- C. Coils shall be aluminum plate fin type with belled collars and shall be bonded to 1/2 inch or 5/8 inch OD copper tubes by mechanical expansion. Coils shall have headers with steel MPT connections. Working pressure shall be 250 psig at 300°F.
- D. All coil segments shall be furnished with 304 stainless steel coil casings and 304 stainless steel coil supports.
- E. Coils shall be drainable and have non-trapping circuits. Headers shall have drain and vent connections extended to the outside of the unit casing. Supply and return headers shall be clearly labeled on the outside of the unit. Provide grommets at all pipe penetrations through cabinet.
- F. Main drain pan shall be double wall stainless steel with minimum 2 inch insulation, sloped toward drain fitting, with integral elbow for side discharge and FPT connection, and shall comply with ASHRAE Std 62.1. A maximum of one drain shall be supplied for each cooling coil section which shall extend at least 16" downstream of the coil (units with a single fan can be reduced to 12"). The unit design shall not require a drain pan in any downstream section to contain the coil condensate. Moisture shall not carry over past the coil. Moisture eliminators are not acceptable for moisture carryover prevention.
- G. Direct expansion coils shall be furnished with a brass distributor with solder type connections. Suction and discharge connections shall be on the same end regardless of rows deep. Coils shall have intertwined circuits for equal operation on each circuit. Provide the number of distributors equal to the amount of refrigerant circuits to the associated condensing unit. Direct expansion coil shall be selected to match the saturated suction temperature and capacity of the associated condensing unit.
- H. Maximum face velocity across cooling coils shall be 500 FPM, unless noted otherwise on equipment schedule.
- I. Coils in series shall have a minimum of 14 inch access section between coil casings.
- J. In units larger than 10,000 cfm, coils shall be removable through a service panel without disassembly of the unit.

2.7 FILTERS

- A. Filter section shall accept 2 inch or 4 inch filters of standard sizes as indicated on drawings and shall be designed and constructed to house the type of filter specified. Section shall include side access slide rails.
- B. A magnahelic differential pressure gauge shall be factory installed and flush mounted on drive side to measure the pressure drop across the filter.
- C. A dirty filter allowance of 0.50" w.g. shall be incorporated into the total static pressure calculation of each air handling unit filter section.
- D. Reference Section 23 41 00 - Air Filters for additional requirements.

2.8 MIXING BOXES AND INLET PLENUMS

- A. Mixing boxes and inlet plenums shall be factory installed unless otherwise indicated on the Mechanical Drawings.
- B. Field fabricated mixing boxes and sheet metal plenums shall be provided by the installing Contractor where indicated on the Mechanical Drawings. When field fabricated mixing boxes are provided, the installing Contractor and EMCS Contractor shall provide outside air and return air motorized control dampers and actuators.
- C. Factory installed mixing boxes, economizer, and/or inlet plenums shall have factory mounted motorized control dampers. Dampers shall be opposed blades and interconnecting outside air, return air, and mixed air (if applicable) type. Installing EMCS Contractor shall furnish damper actuators. All

factory installed mixing boxes shall have a double wall hinged access door on the drive side of the unit.

2.9 ACCESSORIES

- A. All damper blades shall be galvanized steel, double skin airfoil type, housed in a galvanized steel frame and mechanically fastened to a hex axle rod rotating in stainless steel bearings. Dampers shall be sectionalized to limit blade length to no more than 48 inches so as to minimize blade warpage. Blade seals are required to assure tight closure. The damper shall be rated for a maximum leakage rate of 1 percent of nominal airflow at 1 inch w.g.

PART 3 - EXECUTION

3.1 INSTALLATION


- A. If floor mounted air handling units are furnished with internal vibration isolation option, provide 2" thick Amber/Booth type NRC ribbed neoprene pads or approved equal to address high frequency breakout and provide additional unit elevation with overall sufficient height to provide p-trap with one inch greater than the unit total static pressure. Ribbed neoprene pads shall be located in accordance with the air handling unit manufacturer's recommendations. Condensate drain connection shall not penetrate the base air handling unit's rail.
- B. Install in accordance with manufacturer's instructions.
- C. All items required for a complete and proper installation are not necessarily indicated on the plans or in the specifications. Provide all items required as per manufacturer's requirements.
- D. Make electrical connections, taking care that these do not block access to any part of the equipment requiring service.
- E. Unit wiring shall comply with NFPA 70 and all applicable UL standards.
- F. Connect full size condensate drain pipe to air handling unit and extend to nearest drain. Pipe shall be schedule 40 galvanized steel with malleable iron screwed fittings.
- G. Unit installation shall comply with NFPA 90A requirements.
- H. System Startup Requirements: The installing Contractor service technician shall startup all air handling units. Technician shall at a minimum perform the following steps for each unit:
 - 1. Energize the unit disconnect switch.
 - 2. Verify correct voltage, phases and cycles.
 - 3. Energize fan motor and verify correct direction of rotation.
 - 4. Re-check damper operation: verify that unit cannot and will not operate with all dampers in the closed position.
 - 5. Energize fan motors and verify that motor FLA is within manufacturer's tolerance of nameplate FLA for each phase.
- I. Do not operate units for any purpose, temporary or permanent, until ductwork is clean, filters are in place, bearings lubricated, and fans have been test run under observation.
- J. The installing Contractor shall comply with manufacturer's start-up requirements to ensure safe and correct operation.

END OF SECTION


ABBREVIATIONS

Table of abbreviations organized into columns A through Z, listing symbols and their corresponding full names for various HVAC and mechanical components.

DUCTWORK



AIR DEVICE TYPES




WALL MOUNTED SENSOR TYPES

- List of wall mounted sensor types including THERMOSTAT, HUMIDISTAT, CARBON DIOXIDE SENSOR, CARBON MONOXIDE SENSOR, NITROGEN DIOXIDE SENSOR, and ON/OFF SWITCH.

PIPING TYPES

- List of piping types including CONDENSATE DRAIN LINE, CHILLED WATER SUPPLY, CHILLED WATER RETURN, HOT WATER SUPPLY, HOT WATER RETURN, CONDENSER WATER SUPPLY, CONDENSER WATER RETURN, and REFRIGERANT PIPING SIZED BY MFR.

DRAWING/DETAIL REFERENCE KEY



MECHANICAL GENERAL NOTES

- 1. PIPING AND DUCTWORK SHOWN ON PLANS ARE SCHEMATIC ONLY. COORDINATE WITH OTHER TRADES FOR PIPING AND DUCTWORK ROUTING, OFFSET AND RUN PIPING INSIDE THE STRUCTURE IF REQUIRED. PROVIDE ALL NECESSARY PIPING, DUCTWORK, FITTING, INSULATION, AND OTHER ACCESSORIES IN ORDER TO COMPLETE THE INSTALLATIONS.
2. EXACT LOCATIONS OF VAV TERMINAL UNITS, GRILLES, AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
3. EQUIPMENT SIZES, DIMENSIONS, AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE MANUFACTURER DRAWINGS AND CUTSHEETS BEFORE FABRICATING OF DUCTWORK, PIPING, OR POURING OF CONCRETE HOUSEKEEPING FLOORS.
4. SHEET METAL INLET DUCTS TO VAV TERMINAL UNITS SHALL BE SAME SIZE AS THE BOX INLET SIZE. PROVIDE RIGID ROUND DUCT THAT IS ONE SIZE LARGER THAN THE INLET BOX SIZE IF THE DISTANCE BETWEEN THE MAIN DUCT AND THE VAV BOX IS MORE THAN 6'-0".
5. PROVIDE CONICAL SPIN-IN CONNECTOR FOR ALL ROUND DUCT CONNECTIONS TO VAV TERMINAL UNIT INLETS.
6. INSTALL VAV TERMINAL UNITS TO ENSURE ACCESS PANELS ARE NOT BLOCKED. ACCESS FOR SERVICE MUST BE PROVIDED.
7. CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
8. DUCT SIZES SHOWN ON PLANS ARE CLEAR INSIDE DIMENSIONS.
9. PROVIDE RECTANGULAR BRANCH DUCT TAP FOR ALL RECTANGULAR DUCT CONNECTIONS TO RECTANGULAR DUCT TRUNKS.
10. ALL MEDIUM AND LOW PRESSURE DUCTWORK AND ASSOCIATED ACCESSORIES SHALL BE CONSTRUCTED TO MEET THE LATEST SMACNA STANDARDS FOR MEDIUM AND LOW PRESSURE DUCTWORK.
11. ALL OUTSIDE AIR, SUPPLY AIR, AND RETURN AIR DUCTWORK AND PLENUMS SHALL BE INSULATED WITH A MINIMUM OF R-8 INSULATION WHERE LOCATED IN UNCONDITIONED SPACES AND SHALL BE INSULATED WITH A MINIMUM OF R-8 INSULATION WHERE LOCATED OUTSIDE THE BUILDING. REFER TO SPECIFICATION 23 07 13 DUCT INSULATION FOR FURTHER INFORMATION AND ADDITIONAL REQUIREMENTS.
12. ALL DUCTWORK SHALL BE CONSTRUCTED TO SEAL CLASS 'A' AS REFERENCED IN SMACNA STANDARDS. ALL NON-WELDED JOINTS AND SEAMS SHALL BE SEALED. THIS INCLUDES BUT IS NOT LIMITED TO TRANSVERSE JOINTS, LONGITUDINAL SEAMS, DUCT WALL PENETRATIONS, SPIN-INS, TAPS, AND OTHER BRANCH CONNECTIONS, ACCESS DOORS, ACCESS PANELS, AND DUCT CONNECTIONS TO EQUIPMENT. OPENINGS FOR ROTATING SHAFTS SHALL ALSO BE SEALED WITH BUSHINGS. REFER TO SPECIFICATION 23 07 13 METAL DUCTWORK FOR FURTHER INFORMATION.
13. ALL EXPOSED DUCTWORK AND PIPING WITH ASSOCIATED ACCESSORIES IN AREAS WITH NO CEILING OR PARTIAL CEILING SHALL BE PAINTED. REFER TO ARCHITECT FOR COLOR.
14. DIVISION 23 MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE SENSORS AND HUMIDITY SENSORS.
15. PROVIDE REMOTE SPIN-IN DAMPER OPERATOR FOR SPIN-IN CONNECTIONS AND VOLUME DAMPERS LOCATED OVER GYPSUM CEILINGS.
16. PROVIDE AIRFOIL TYPE TURNING VANES IN ALL 90 DEGREE ELBOWS.
17. COORDINATE LOCATIONS OF FLOOR AND WALL OPENINGS WITH ARCHITECT AND STRUCTURAL ENGINEER.
18. ALL CEILING MOUNTED AND WALL MOUNTED AIR DEVICE FINISHES SHALL MATCH ADJACENT ARCHITECTURAL SURFACE. CONTRACTOR SHALL COORDINATE COLOR WITH ARCHITECT.
19. NO PIPE HANGERS SHALL BE SPACED MORE THAN 10'-0" O.C. COMPLY WITH PIPE SPACING AS SPECIFIED IN THE PIPING SUPPORT SPECIFICATIONS.
20. MECHANICAL CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF ALL OUTSIDE AIR INTAKES TO MAINTAIN 15 FEET DISTANCE BETWEEN OUTSIDE AIR INTAKES AND ANY EXHAUST AIR OUTLET, FLUES OR PLUMBING VENTS.
21. MECHANICAL CONTRACTOR SHALL COORDINATE WITH PLUMBING CONTRACTOR FOR ALL CONDENSATE DRAIN PIPES CONNECTING TO A SINK DRAIN TAIL PIECE.
22. CONTRACTOR SHALL CUT AND REMOVE PORTIONS OF "HARD CEILINGS" AS NECESSARY TO INSTALL NEW EQUIPMENT. CONTRACTOR SHALL RE-PAINT ALL HARD CEILINGS TO MATCH EXISTING CONDITIONS. ANY DAMAGED "LAY-IN" CEILINGS DAMAGED DURING THE REMOVAL PROCESS SHALL BE REPLACED WITH NEW "CEILING TILES" AT CONTRACTOR'S EXPENSE.
23. WHERE NEW SPRINKLER HEADS MUST BE ADDED UNDER FIXED OBSTRUCTIONS (DUCTWORK) OVER 4 FEET WIDE PER NFPA 13, 8.6.5.3.3, PROVIDE PIPING, FITTINGS, JOINING METHODS, AND SPRINKLER HEADS TO MATCH EXISTING TYPE. FIELD VERIFY.

CONTROLS SCHEMATIC SYMBOLS LEGEND

- Legend of controls schematic symbols including ANALOG INPUT, ANALOG OUTPUT, DIGITAL/BINARY INPUT, DIGITAL/BINARY OUTPUT, ON-OFF MOTORIZED DAMPER, MODULATING TYPE MOTORIZED DAMPER, AIR FLOW MEASURING STATION, CONTROL VALVE MODULATING TYPE, VARIABLE FREQUENCY DRIVE, CURRENT SENSING RELAY, FREEZE/STAT, HIGH STATIC LIMIT, STATIC PRESSURE TRANSMITTER, DIFFERENTIAL PRESSURE TRANSDUCER, FLOW METER, FLOW SWITCH, DISCHARGE AIR TEMPERATURE SENSOR, WALL SENSOR, THERMOSTAT, CARBON DIOXIDE SENSOR, SET POINT, SUPPLY AIR, RETURN AIR, OUTSIDE AIR, HEATING COIL, COOLING COIL, DIRECT EXPANSION COOLING COIL, PRESSURE INDEPENDENT CHARACTERIZED CONTROL VALVE, AIRFLOW CROSS, and DIFFERENTIAL PRESSURE SWITCH.

MECHANICAL PIPING SYMBOLS

- Legend of mechanical piping symbols including CONDENSER WATER SUPPLY, CONDENSER WATER RETURN, CHILLED WATER SUPPLY, CHILLED WATER RETURN, CONDENSATE DRAIN LINE, CAP ON END OF PIPE, ELBOW UP, ELBOW DOWN, VALVE IN DROP, VALVE IN RISE, DIRECTION OF FLOW, DIRECTION OF SLOPE DOWN, CONCENTRIC REDUCER, ECCENTRIC REDUCER, TEE OUTLET UP, TEE OUTLET DOWN, UNION, FLANGE, PIPE ANCHOR, EXPANSION JOINT, PRESSURE AND TEMPERATURE TAP, FLOW VENTURI, VACUUM BREAKER, VACUUM RELIEF VALVE, BACKFLOW PREVENTOR, THERMOMETER, CIRCULATING PUMP, STRAINER WITH BLOW DOWN VALVE, GLOBE VALVE, BALL VALVE, BALANCING VALVE WITH DIFFERENTIAL PRESSURE TAPS, OS&Y VALVE, CHECK VALVE, BUTTERFLY VALVE, TWO-WAY MODULATING CONTROL VALVE, THREE-WAY MODULATING CONTROL VALVE, SOLENOID VALVE, PRESSURE REDUCING VALVE, GAS REGULATOR, GAS COCK, SPRINKLER FLOOR CONTROL STATION, MANUAL AIR VENT, AUTOMATIC AIR VENT, T&P RELIEF VALVE, PRESSURE GAUGE WITH GAUGE COCK, STEAM TRAP, WATER METER, and FLEXIBLE CONNECTION.



Revision table with columns for No., DATE, and DESCRIPTION. Includes revisions 01 and 02.




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE: 4/7/2022
DRAWN BY: DBR
CHECKED BY: DBR
PROJECT NUMBER: 218007.002
SHEET TITLE: MECHANICAL LEGEND

MECHANICAL LEGEND
SHEET NUMBER: M0.01
DBR Project Number: 218007.002
HA JA JB ---

Plotted: Apr 7, 2022 10:48 PM by user: rblacks
 C:\Users\rblacks\OneDrive\Documents\Drawings\04\218007-002_DEMO.dwg



1 LEVEL 1 MECHANICAL DEMO PLAN - F
 MD2.12F 1/8" = 1'-0"

MECHANICAL DEMO GENERAL NOTES:

- A. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD, SO THEY HAVE OBTAINED THE SCOPE OF THE MECHANICAL DEMOLITION WORK INVOLVED AS A RESULT OF MODIFICATIONS TO THE EXISTING STRUCTURE. THE SCOPE OF WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT, OR APPARATUS WHICH MAY BE RELOCATED, OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE RELOCATED OR REMOVED EITHER ACCOMPLISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON DRAWINGS, CONTRACTOR SHALL DEMOLISH ONLY WHAT IS INDICATED TO BE DEMOLISHED ON DRAWINGS.
- B. CONTRACTOR SHALL COORDINATE WITH OWNER FOR ALL EQUIPMENT BEING REMOVED. OWNER SHALL RESERVE THE RIGHT TO CLAIM ALL EQUIPMENT, DUCTWORK, AND AIR DEVICES REMOVED DURING DEMOLITION.
- C. CONTRACTOR TO REPORT ANY DAMAGED EQUIPMENT THAT IS SHOWN AS EXISTING TO REMAIN TO THE OWNER PRIOR TO STARTING ALL WORK. ALL EQUIPMENT FOUND TO BE DAMAGED AT THE TIME OF SUBSTANTIAL COMPLETION, THAT HAD NOT BEEN REPORTED PRIOR TO CONSTRUCTION, CONTRACTOR TO REPAIR AT THEIR OWN COST.
- D. ALL REMOVED EQUIPMENT WITH ACCESS TO DUCTWORK, SHAFTS, OR PIPING, SHALL HAVE ALL CONNECTIONS TO THESE MATERIAL CLEANED, WHERE THE MATERIALS ARE REUSED, FOR EXAMPLE, EXHAUST SHAFTS THAT ARE SCHEDULED FOR REUSE AND SHALL BE CLEANED TO THE FULLEST EXTENT POSSIBLE. NOTIFY ARCHITECT/ENGINEER TEAM OF ANY DEFICIENCIES FOUND UPON REMOVAL OF HVAC SYSTEM, THAT ARE NOT INDICATED IN THESE PLANS AND SPECIFICATIONS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. ALL EXISTING DUCTWORK AND EQUIPMENT TO BE REUSED MUST BE CLEANED, PAINTED, AND ALL DAMAGED PARTS MUST BE REPAIRED OR REPLACED.
- G. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- H. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

MECHANICAL DEMOLITION KEY NOTES:

- 1. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEWS CONTINUATION.
- 2. EXISTING T-STAT, HUMIDITY SENSOR, CO2 SENSOR, AND CONDUCTORS SHALL BE REMOVED. EXISTING J-BOX SHALL REMAIN FOR RE-USE.
- 3. NOT USED.
- 4. EQUIPMENT LOCATED ON ROOF.
- 5. CONTRACTOR SHALL DEMOLISH HOT WATER PIPING TO ROOF TOP UNIT AND ABANDON HOT WATER COIL. UNIT WILL RECEIVE AN ELECTRIC DUCT HEATER. COORDINATE WITH NEW WORK REQUIREMENTS, REFERENCE SITE PLAN FOR HOT WATER PIPING ROUTING.

LEGEND:

- EXISTING TO BE DEMOLISHED
- EXISTING TO REMAIN



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	LEVEL 1 MECHANICAL DEMO PLAN - F

LEVEL 1 MECHANICAL DEMO PLAN - F



SHEET NUMBER:

MD2.12F



HA	JA	JB	---	---
----	----	----	-----	-----

Plotted: Apr 7, 2022, 4:18 PM by user: rjclark
 C:\Users\rjclark\OneDrive\Documents\Drawings\04-218007-002_DEMO.dwg



1 LEVEL 1 MECHANICAL DEMO PLAN - G
 1/8" = 1'-0"


MECHANICAL DEMO GENERAL NOTES:

- A. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD, SO THEY HAVE OBTAINED THE SCOPE OF THE MECHANICAL DEMOLITION WORK INVOLVED AS A RESULT OF MODIFICATIONS TO THE EXISTING STRUCTURE. THE SCOPE OF WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT, OR APPARATUS WHICH MAY BE REROUTED, RELOCATED, OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE REROUTED OR REMOVED EITHER ACCOMPISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON DRAWINGS, CONTRACTOR SHALL DEMOLISH ONLY WHAT IS INDICATED TO BE DEMOLISHED ON DRAWINGS.
- B. CONTRACTOR SHALL COORDINATE WITH OWNER FOR ALL EQUIPMENT BEING REMOVED. OWNER SHALL RESERVE THE RIGHT TO CLAIM ALL EQUIPMENT, DUCTWORK, AND AIR DEVICES REMOVED DURING DEMOLITION.
- C. CONTRACTOR TO REPORT ANY DAMAGED EQUIPMENT THAT IS SHOWN AS EXISTING TO REMAIN TO THE OWNER PRIOR TO STARTING ALL WORK. ALL EQUIPMENT FOUND TO BE DAMAGED AT THE TIME OF SUBSTANTIAL COMPLETION, THAT HAD NOT BEEN REPORTED PRIOR TO CONSTRUCTION, CONTRACTOR TO REPAIR AT THEIR OWN COST.
- D. ALL REMOVED EQUIPMENT WITH ACCESS TO DUCTWORK, SHAFTS, OR PIPING, SHALL HAVE ALL CONNECTIONS TO THESE MATERIAL CLEANED, WHERE THE MATERIALS ARE REUSED. FOR EXAMPLE, EXHAUST SHAFTS THAT ARE SCHEDULED FOR REUSE AND SHALL BE CLEANED TO THE FULLEST EXTENT POSSIBLE. NOTIFY ARCHITECT/ENGINEER TEAM OF ANY DEFICIENCIES FOUND UPON REMOVAL OF HVAC SYSTEM, THAT ARE NOT INDICATED IN THESE PLANS AND SPECIFICATIONS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. ALL EXISTING DUCTWORK AND EQUIPMENT TO BE REUSED MUST BE CLEANED, PAINTED, AND ALL DAMAGED PARTS MUST BE REPAIRED OR REPLACED.
- G. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- H. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

MECHANICAL DEMOLITION KEY NOTES:

1. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEWS CONTINUATION.
2. EXISTING T-STAT AND CONDUCTORS SHALL BE REMOVED. EXISTING J-BOX SHALL REMAIN FOR RE-USE.
3. EQUIPMENT LOCATED ON ROOF.

LEGEND:



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	LEVEL 1 MECHANICAL DEMO PLAN - G
SHEET NUMBER:	MD2.13G

TRUE NORTH
 PLAN NORTH


DBR Project Number: 218007.002
 HA JA JB




1 LEVEL 1F DEMO EXAHU-14 AND EXAHU-15
MD3.12 1/4" = 1'-0"




4 LEVEL 1E DEMO EXAHU-16
MD3.12 1/4" = 1'-0"




2 LEVEL 1 DEMO HYDRONIC PIPING EXAHU-14 AND EXAHU-15
MD3.12 1/4" = 1'-0"




3 LEVEL 1E DEMO EXAHU-17
MD3.12 1/4" = 1'-0"




6 LEVEL 1E DEMO EXAHU-18
MD3.12 1/4" = 1'-0"




7 LEVEL 1E DEMO HYDRONIC PIPING EXAHU-18
MD3.12 1/4" = 1'-0"



5 LEVEL 1E DEMO HYDRONIC PIPING EXAHU-16
MD3.12 1/4" = 1'-0"



8 LEVEL 1G DEMO EXRTU-19 AND EXRTU-20
MD3.12 1/4" = 1'-0"



9 LEVEL 1G DEMO EXAHU-21 AND EXAHU-22
MD3.12 1/4" = 1'-0"

MECHANICAL DEMO GENERAL NOTES:


- A. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD, SO THEY HAVE OBTAINED THE SCOPE OF THE MECHANICAL DEMOLITION WORK INVOLVED AS A RESULT OF MODIFICATIONS TO THE EXISTING STRUCTURE. THE SCOPE OF WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT OR APPARATUS WHICH MAY BE REROUTED, RELOCATED, OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE REROUTED OR REMOVED EITHER ACCOMPISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON DRAWINGS, CONTRACTOR SHALL DEMOLISH ONLY WHAT IS INDICATED TO BE DEMOLISHED ON DRAWINGS.
- B. CONTRACTOR SHALL COORDINATE WITH OWNER FOR ALL EQUIPMENT BEING REMOVED. OWNER SHALL RESERVE THE RIGHT TO CLAIM ALL EQUIPMENT, DUCTWORK, AND AIR DEVICES REMOVED DURING DEMOLITION.
- C. CONTRACTOR TO REPORT ANY DAMAGED EQUIPMENT THAT IS SHOWN AS EXISTING TO REMAIN TO THE OWNER PRIOR TO STARTING ALL WORK. ALL EQUIPMENT FOUND TO BE DAMAGED AT THE TIME OF SUBSTANTIAL COMPLETION, THAT HAD NOT BEEN REPORTED PRIOR TO CONSTRUCTION, CONTRACTOR TO REPAIR AT THEIR OWN COST.
- D. ALL REMOVED EQUIPMENT WITH ACCESS TO DUCTWORK, SHAFTS, OR PIPING, SHALL HAVE ALL CONNECTIONS TO THESE MATERIAL CLEANED, WHERE THE MATERIALS ARE REUSED. FOR EXAMPLE, EXHAUST SHAFTS THAT ARE SCHEDULED FOR REUSE AND SHALL BE CLEANED TO THE FULLEST EXTENT POSSIBLE. NOTIFY ARCHITECT/ENGINEER TEAM OF ANY DEFICIENCIES FOUND UPON REMOVAL OF HVAC SYSTEM, THAT ARE NOT INDICATED IN THESE PLANS AND SPECIFICATIONS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. ALL EXISTING DUCTWORK AND EQUIPMENT TO BE REUSED MUST BE CLEANED, PAINTED, AND ALL DAMAGED PARTS MUST BE REPAIRED OR REPLACED.
- G. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- H. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

MECHANICAL DEMOLITION KEY NOTES:

1. EXISTING AIR HANDLING UNIT TO BE REMOVED IN ITS ENTIRETY. REMOVE THE SUPPLY, RETURN (WHERE APPLICABLE), AND OUTSIDE AIR DUCT AS INDICATED. REMOVE EXISTING BUILDING AUTOMATION SENSORS.
2. HOUSE KEEPING PAD SHALL REMAIN AND BE MODIFIED AND NECESSARY TO ACCOMMODATE THE NEW AIR HANDLING UNIT FOOTPRINT. COORDINATE WITH NEW WORK REQUIREMENTS AND EXISTING FLOOR DRAINS. FIELD VERIFY EXISTING CONDITIONS.
3. CONTRACTOR SHALL DEMOLISH EXISTING CONDENSING UNIT, ASSOCIATED REFRIGERANT PIPING BETWEEN CONDENSING UNIT AND AHU, AND ROOF CURB. PATCH AND REPAIR ROOF TO MATCH EXISTING. CONTRACTOR SHALL COORDINATE WITH ROOF MANUFACTURER FOR RECOMMENDED PATCHING METHODS TO MAINTAIN ROOF WARRANTY. COORDINATE WITH NEW WORK REQUIREMENTS.
4. REMOVE EXISTING FIRE DAMPER AS INDICATED. PROVIDE NEW FIRE DAMPER AND SEAL WALL PENETRATION IN ORDER TO MAINTAIN EXISTING FIRE RATING. COORDINATE WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
5. REMOVE EXISTING CHILLED WATER PIPING AS INDICATED.
6. EXISTING DUCT MOUNTED HOT WATER COIL TO BE REMOVED IN ITS ENTIRETY.
7. REMOVE EXISTING HWS/R LINES INCLUSIVE OF MAINS, BRANCHES, RISERS, VALVES, ACCESSORIES, ETC. AS INDICATED. SEAL WALL PENETRATION IN ORDER TO MAINTAIN EXISTING FIRE RATING.
8. REMOVE EXISTING REFRIGERANT PIPING BETWEEN CONDENSING UNIT AND AHU. PIPING IN WALLS SHALL BE CAPPED AND ABANDONED. SEAL WALL PENETRATION IN ORDER TO MAINTAIN EXISTING FIRE RATING.
9. REMOVE EXISTING CONTROL DAMPER AND ACTUATOR. COORDINATE WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
10. REMOVE EXISTING ROOFTOP UNIT AND ASSOCIATED CONDENSATE PIPING. REMOVE EXISTING ROOF CURB TO DECK. REMOVE DUCTWORK AS INDICATED. CONTRACTOR SHALL COORDINATE WITH ROOF MANUFACTURER FOR RECOMMENDED PATCHING METHODS TO MAINTAIN ROOF WARRANTY.
11. REMOVE EXISTING ELECTRIC DUCT HEATER.
12. EQUIPMENT LOCATED ON ROOF.
13. EQUIPMENT LOCATED ON MEZZANINE.
14. EQUIPMENT SUSPENDED ABOVE CEILING.

LEGEND:

- EXISTING TO BE DEMOLISHED
- EXISTING TO REMAIN



DBR
9990 Richmond Avenue, South Building, Suite 300
Houston, Texas 77042
713.914.0888 p 713.914.0888 f


TBPE Firm Registration No. 2234

DBR Project Number 218007.002

HA JA JB

DBR
210.546.0200 v 210.546.0201 f
9601 McAllister Freeway, Suite 410
San Antonio, Texas 78216
TBPE Firm Registration No. 2234

REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE: 4/7/2022
DRAWN BY: DBR
CHECKED BY: DBR
PROJECT NUMBER: 218007.002
SHEET TITLE:

ENLARGED MECHANICAL DEMO PLAN

SHEET NUMBER:
MD3.12

Plotted: Apr 7, 2022, 8:48 PM by user: dbrodriguez
 C:\Users\jenma\OneDrive\Documents\218007.002 - DEMO.dwg

REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



1 LEVEL 1H DEMO CHILLED WATER PLANT
MD3.13 1/4" = 1'-0"

MECHANICAL DEMO GENERAL NOTES:

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD, SO THEY HAVE OBTAINED THE SCOPE OF THE MECHANICAL DEMOLITION WORK INVOLVED AS A RESULT OF MODIFICATIONS TO THE EXISTING STRUCTURE. THE SCOPE OF WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT, OR APPARATUS WHICH MAY BE REROUTED, RELOCATED, OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE REROUTED OR REMOVED OTHER ACCOMPLISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON DRAWINGS. CONTRACTOR SHALL DEMOLISH ONLY WHAT IS INDICATED TO BE DEMOLISHED ON DRAWINGS.
- CONTRACTOR SHALL COORDINATE WITH OWNER FOR ALL EQUIPMENT BEING REMOVED. OWNER SHALL RESERVE THE RIGHT TO CLAM ALL EQUIPMENT, DUCTWORK, AND AIR DEVICES REMOVED DURING DEMOLITION.
- CONTRACTOR TO REPORT ANY DAMAGED EQUIPMENT THAT IS SHOWN AS EXISTING TO REMAIN TO THE OWNER PRIOR TO STARTING ALL WORK. ALL EQUIPMENT FOUND TO BE DAMAGED AT THE TIME OF SUBSTANTIAL COMPLETION, THAT HAD NOT BEEN REPORTED PRIOR TO CONSTRUCTION, CONTRACTOR TO REPAIR AT THEIR OWN COST.
- ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- ALL EXISTING DUCTWORK AND EQUIPMENT TO BE REUSED MUST BE CLEANED, PAINTED, AND ALL DAMAGED PARTS MUST BE REPAIRED OR REPLACED.
- CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

MECHANICAL DEMOLITION KEY NOTES:

- CONTRACTOR SHALL REMOVE EXISTING CHILLED WATER PIPE INCLUSIVE OF MAINS, BRANCHES, RISERS, VALVES, ETC. AS INDICATED ON PLAN. COORDINATE EXTENT OF DEMOLITION WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL REMOVE EXISTING HOT WATER PIPE INCLUSIVE OF MAINS, BRANCHES, RISERS, VALVES, ETC. AS INDICATED ON PLAN. COORDINATE EXTENT OF DEMOLITION WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL DEMOLISH EXISTING CHILLED WATER PUMPS AS INDICATED. HOUSE KEEPING PAD SHALL REMAIN AND BE MODIFIED AS NECESSARY TO ACCOMMODATE NEW PUMPS AND EQUIPMENT. COORDINATE WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL DEMOLISH EXISTING CHILLED WATER PUMPS AND HOUSE KEEPING PAD AS INDICATED. COORDINATE WITH NEW WORK REQUIREMENTS. FIELD VERIFY EXISTING CONDITIONS.
- REMOVE EXISTING LOUVER AS INDICATED. PATCH AND REPAIR WALL AND BASE FINISH TO MATCH EXISTING ADJACENT SURFACES. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL DEMOLISH EXISTING BOILER 1, BOILER 2 AND ASSOCIATED HP-1 THRU HP-4 IN ITS ENTIRETY AND DISPOSE OF PROPERLY. CONTRACTOR SHALL DISCONNECT VENT, ELECTRICAL, WATER CONNECTIONS, GAS CONNECTION AND BUILDING AUTOMATION WIRING. PATCH AND REPAIR ROOF TO MATCH EXISTING. CONTRACTOR SHALL COORDINATE WITH ROOF MANUFACTURER FOR RECOMMENDED PATCHING METHODS TO MAINTAIN ROOF WARRANTY.
- REMOVE EXISTING LOUVER AS INDICATED. PATCH AND REPAIR WALL AND BASE FINISH TO MATCH EXISTING ADJACENT SURFACES. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL REMOVE FLUE PIPING, CAP ROOF CAP, AND MAKE WATERTIGHT.
- CONTRACTOR SHALL PATCH AND REPAIR WALL AND BASE FINISH TO MATCH EXISTING ADJACENT SURFACES. FIELD VERIFY EXISTING CONDITIONS.
- CONTRACTOR SHALL DEMOLISH EXISTING THERMAL STORAGE MODULES IN THEIR ENTIRETY AND DISPOSE OF PROPERLY.

LEGEND:



- EXISTING TO BE DEMOLISHED
- EXISTING TO REMAIN

EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:
4/7/2022
DRAWN BY:
DBR
CHECKED BY:
DBR
PROJECT NUMBER:
218007.002
SHEET TITLE:


ENLARGED
MECHANICAL DEMO
PLAN

SHEET NUMBER:
MD3.13

9990 Richmond Avenue, South Building, Suite 300
Houston, Texas 77042
713.914.0888 p 713.914.0886 f
TBPE Firm Registration No. 2234
DBR Project Number 218007.002
HA JA JB

Plotted: Apr 7, 2022, 4:21 PM by user: rjclark, Sheet: 4/7/2022, by user: rjclark
 C:\Users\rjclark\OneDrive\Documents\Drawings\218007-002 (RT RECOVERED FILE DO NOT DELETE)\DWG



MECHANICAL GENERAL NOTES:

- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- C. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- D. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- E. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

MECHANICAL KEY NOTES:

- 1. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEWS CONTINUATION.
- 2. PROVIDE NEW CHILLED WATER BYPASS VALVE EQUAL TO BELIMO B62505-70 WITH BELIMO AF824-MFT-S ACTUATOR. REFER TO DETAIL 10/MS.02.
- 3. DIFFERENTIAL PRESSURE SENSOR.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002

SHEET TITLE:
COMPOSITE LEVEL 1 MECHANICAL HYDRONIC PIPING PLAN

SHEET NUMBER:


M1.11

COMPOSITE LEVEL 1 MECHANICAL HYDRONIC PIPING PLAN
 3/32" = 1'-0"



DRR Project Number	218007.002			
HA	JA	JB	---	---

Plotted: Apr 7, 2022, 4:27 PM by user: rblucas
 C:\Users\rblucas\OneDrive\Documents\Drawings\218007\002 (RT RECOVERED FILE DO NOT DELETE).DWG



1 LEVEL 1 MECHANICAL PLAN - A
 M2.11A 1/8" = 1'-0"

MECHANICAL GENERAL NOTES:

- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- C. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- D. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- G. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- H. EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

1. APPROXIMATE LOCATION OF NEW SINGLE DUCT BOX. CONTRACTOR SHALL INSTALL NEW SINGLE DUCT BOX IN EXISTING DUCTWORK. PROVIDE DUCT TRANSITIONS TO BOX INLET AND OUTLET AS REQUIRED. CONTRACTOR SHALL REMOVE AND PATCH EXISTING DUCTWORK AS NECESSARY. TYP.
2. NEW DDC TEMPERATURE, RELATIVE HUMIDITY, AND CO2 SENSORS.
3. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEW CONTINUATION.
4. PROVIDE NEW MANUAL BALANCING DAMPER.

LEGEND:


- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT




REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542




DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	LEVEL 1 MECHANICAL PLAN - A



DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p. 713.914.0886 f.
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002

SHEET NUMBER:
M2.11A

P:\Arch\4-7-2022_12 PM\user:rlc\Drawings\218007-002\RT RECOVERED FILE DO NOT DELETE\DWG
 C:\Users\rlc\OneDrive\Documents\218007-002 - EGS2 - Daird Wils HVAC Improvements - MMS\Project Files\Drawings\04\218007-002 (RT RECOVERED FILE DO NOT DELETE).DWG



1 LEVEL 1 MECHANICAL PLAN - B
 M2.11B 1/8" = 1'-0"

MECHANICAL GENERAL NOTES:

- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- C. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- D. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- G. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- H. EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

- 1. APPROXIMATE LOCATION OF NEW SINGLE DUCT BOX. CONTRACTOR SHALL INSTALL NEW SINGLE DUCT BOX IN EXISTING DUCTWORK. PROVIDE DUCT TRANSITIONS TO BOX INLET AND OUTLET AS REQUIRED. CONTRACTOR SHALL REMOVE AND PATCH EXISTING DUCTWORK AS NECESSARY. TYP.
- 2. NEW DDC TEMPERATURE, RELATIVE HUMIDITY, AND CO2 SENSORS.
- 3. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEW CONTINUATION.
- 4. PROVIDE NEW MANUAL BALANCING DAMPER.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



REVISION		
No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	


**LEVEL 1
 MECHANICAL
 PLAN - B**

SHEET NUMBER:

M2.11B



Plotted: Apr 7, 2022, 4:27 PM by user: rblacis
 C:\Users\rblacis\OneDrive\Documents\Drawings\04-218007-002 (RT RECOVERED FILE DO NOT DELETE).DWG



1 LEVEL 1 MECHANICAL PLAN - C
 M2.11C 1/8" = 1'-0"

MECHANICAL GENERAL NOTES:

- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- C. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- D. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- G. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- H. EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

- 1. APPROXIMATE LOCATION OF NEW SINGLE DUCT BOX. CONTRACTOR SHALL INSTALL NEW SINGLE DUCT BOX IN EXISTING DUCTWORK. PROVIDE DUCT TRANSITIONS TO BOX INLET AND OUTLET AS REQUIRED. CONTRACTOR SHALL REMOVE AND PATCH EXISTING DUCTWORK AS NECESSARY. TYP.
- 2. NEW DDC TEMPERATURE, RELATIVE HUMIDITY, AND CO2 SENSORS.
- 3. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEW CONTINUATION.
- 4. PROVIDE NEW MANUAL BALANCING DAMPER.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



210.546.0200 v. 210.546.0201 f
 9601 McAllister Freeway, Suite 410
 San Antonio, Texas 78216
 TBPE Firm Registration NO. 2234

REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	

LEVEL 1 MECHANICAL PLAN - C


SHEET NUMBER:

M2.11C



9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p. 713.914.0886 f.
 TBPE Firm Registration No. 2234
 DBR Project Number: 218007.002
 HA JA JB

P:\Arch\4-7-2022_42 PM\user:rlc\Drawings\218007.002\218007.002.dwg (RT RECOVERED FILE DO NOT DELETE) DWG
 C:\Users\rlcna\OneDrive\Documents\218007.002 - EGS2 - Daird Wils HVAC Improvements - MMS\Project Files\Drawings\04\218007.002 (RT RECOVERED FILE DO NOT DELETE) DWG



1 LEVEL 1 MECHANICAL PLAN - D
 1/8" = 1'-0"

MECHANICAL GENERAL NOTES:

- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- C. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- D. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- G. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- H. EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

1. APPROXIMATE LOCATION OF NEW SINGLE DUCT BOX. CONTRACTOR SHALL INSTALL NEW SINGLE DUCT BOX IN EXISTING DUCTWORK. PROVIDE DUCT TRANSITIONS TO BOX INLET AND OUTLET AS REQUIRED. CONTRACTOR SHALL REMOVE AND PATCH EXISTING DUCTWORK AS NECESSARY. TYP.
2. NEW ODC TEMPERATURE, RELATIVE HUMIDITY, AND CO2 SENSORS.
3. REFER TO ENLARGED MECHANICAL ROOM PLANS FOR MECHANICAL ROOM VIEW CONTINUATION.
4. PROVIDE NEW MANUAL BALANCING DAMPER.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	

LEVEL 1 MECHANICAL PLAN - D


TRUE NORTH
 PLAN NORTH

9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p 713.914.0886 f
 TBPE Firm Registration No. 2234

DBR Project Number 218007.002
 HA JA JB

SHEET NUMBER:	M2.11D
---------------	--------

REVISION	No.	DATE	DESCRIPTION
	01	5/23/2022	ADDENDUM #1
	02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	

ENLARGED
 MECHANICAL ROOM
 PLANS


SHEET NUMBER:	M3.10			
DBR Project Number	218007.002			
HA	JA	JB	----	----




7 LEVEL 1D MECHANICAL AHU-6+7
 M3.10 1/4" = 1'-0"




8 LEVEL 1D HYDRONIC PIPING AHU-6+7
 M3.10 1/4" = 1'-0"




5 LEVEL 1C MECHANICAL AHU-4+5
 M3.10 1/4" = 1'-0"




6 LEVEL 1C HYDRONIC PIPING AHU-4+5
 M3.10 1/4" = 1'-0"




3 LEVEL 1B MECHANICAL AHU-3
 M3.10 1/4" = 1'-0"



4 LEVEL 1B HYDRONIC PIPING AHU-3
 M3.10 1/4" = 1'-0"



1 LEVEL 1A MECHANICAL AHU-1+2
 M3.10 1/4" = 1'-0"



2 LEVEL 1A HYDRONIC PIPING AHU-1+2
 M3.10 1/4" = 1'-0"

MECHANICAL GENERAL NOTES:



- REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

- MODIFY EXISTING HOUSE KEEPING PAD TO ACCOMMODATE THE NEW AIR HANDLING UNIT.
- INSTALL SUPPLY AND RETURN AIR DUCTWORK AS INDICATED AND AS REQUIRED. FIELD VERIFY REQUIREMENT OF CONNECTION.
- CONTRACTOR SHALL PROVIDE A NEW FULL SIZE INSULATED COPPER CONDENSATE DRAIN LINE. PROVIDE PIPE SUPPORT MAXIMUM 5'-0" O.C. SPACING. SLOPE PIPING 1/8" PER FOOT. ROUTE AND DRAIN CONDENSATE LINE INDIRECTLY INTO NEAREST FLOOR SINK. REFER TO DETAIL 26/M6.01 FOR REQUIREMENTS.
- PROVIDE AND INSTALL MODULATING CONTROL DAMPER WITH AFMS IN OUTSIDE AIR DUCT. DAMPER SHALL BE EQUAL TO RUSKIN MODEL "JAGSOX", HIGH PERFORMANCE, AIRFOL, OPPOSED BLADE.
- VFD SHALL BE PROVIDED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR.
- DUCT MOUNTED STATIC PRESSURE SENSOR.
- PROVIDE NEW FIRE DAMPER.
- CONTRACTOR SHALL ROUTE AND CONNECT EXISTING CHILLED WATER SUPPLY AND RETURN LINES TO THE NEW AIR HANDLING UNIT.
- PROVIDE AND INSTALL MODULATING CONTROL DAMPER IN OUTSIDE AIR DUCT. DAMPER SHALL BE EQUAL TO RUSKIN MODEL "C860", HIGH PERFORMANCE, AIRFOL, OPPOSED BLADE.
- CONNECT BUILDING RELIEF AIR DUCT TO RETURN AIR DUCT. PROVIDE NEW MANUAL BALANCING DAMPER. BALANCE RELIEF AIR DUCT TO 3,600 CFM.
- CONNECT BUILDING RELIEF AIR DUCT TO RETURN AIR DUCT. PROVIDE NEW MANUAL BALANCING DAMPER. BALANCE RELIEF AIR DUCT TO 3,160 CFM.


LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



Plotted: Aug 7, 2022 7:46 PM by user: rht@db... Saved: 4/7/2022 by user: rht@db...
 C:\Users\rht@db... \AppData\Local\Temp\218007.002 - EC(S)2 - District Wide HVAC Improvements - MMS\Project Files\Drawings\04-218007.002 (PT RECOVERED FILE DO NOT DELETE).DWG

REVISION	No.	DATE	DESCRIPTION
	01	5/23/2022	ADDENDUM #1
	02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	

ENLARGED
 MECHANICAL ROOM
 PLANS


SHEET NUMBER:	M3.11			
DBR Project Number	218007.002			
HA	JA	JB	---	---




7 LEVEL 2B MECHANICAL AHU-10
 M3.11 1/4" = 1'-0"




8 LEVEL 2B HYDRONIC PIPING AHU-10
 M3.11 1/4" = 1'-0"




9 LEVEL 2D MECHANICAL AHU-13
 M3.11 1/4" = 1'-0"




10 LEVEL 2D HYDRONIC PIPING AHU-13
 M3.11 1/4" = 1'-0"




4 LEVEL 2B MECHANICAL AHU-9
 M3.11 1/4" = 1'-0"




5 LEVEL 2B HYDRONIC PIPING AHU-9
 M3.11 1/4" = 1'-0"




1 LEVEL 2A MECHANICAL AHU-8
 M3.11 1/4" = 1'-0"



2 LEVEL 2A HYDRONIC PIPING AHU-8
 M3.11 1/4" = 1'-0"



3 LEVEL 2C MECHANICAL AHU-11
 M3.11 1/4" = 1'-0"



6 LEVEL 2C HYDRONIC PIPING AHU-11
 M3.11 1/4" = 1'-0"

MECHANICAL GENERAL NOTES:


- A. REFER TO SHEET M0.01 FOR MECHANICAL GENERAL NOTES.
- B. EXACT LOCATIONS OF HOT WATER DUCT COILS AND DAMPERS SHALL BE FIELD COORDINATED WITH OTHER TRADES TO AVOID CONFLICTS AND ALLOW ADEQUATE CLEARANCES.
- C. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- D. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
- E. ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
- F. CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
- G. CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.
- H. EXISTING DUCTWORK SHOWN AS A SINGLE LINE.

MECHANICAL KEY NOTES:

1. MODIFY EXISTING HOUSE KEEPING PAD TO ACCOMMODATE THE NEW AIR HANDLING UNIT.
2. INSTALL SUPPLY AND RETURN AIR DUCTWORK AS INDICATED AND AS REQUIRED. FIELD VERIFY REQUIREMENT OF CONNECTION.
3. CONTRACTOR SHALL PROVIDE A NEW FULL SIZE INSULATED COPPER CONDENSATE DRAIN LINE. PROVIDE PIPE SUPPORT MAXIMUM 5'-0" O.C. SLOPING. SLOPE PIPING 1/8" PER FOOT. ROUTE AND DRAIN CONDENSATE LINE INDIRECTLY INTO NEAREST FLOOR SINK. REFER TO DETAIL 29/M0.01 FOR REQUIREMENTS.
4. PROVIDE AND INSTALL MODULATING CONTROL DAMPER WITH AFMS IN OUTSIDE AIR DUCT. DAMPER SHALL BE EQUAL TO RUSKIN MODEL "1A050X", HIGH PERFORMANCE, AIRFOIL, OPPOSED BLADE.
5. VFD SHALL BE PROVIDED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR.
6. DUCT MOUNTED STATIC PRESSURE SENSOR.
7. PROVIDE NEW FIRE DAMPER.
8. CONTRACTOR SHALL ROUTE AND CONNECT EXISTING CHILLED WATER SUPPLY AND RETURN LINES TO THE NEW AIR HANDLING UNIT.
9. PROVIDE AND INSTALL MODULATING CONTROL DAMPER IN OUTSIDE AIR DUCT. DAMPER SHALL BE EQUAL TO RUSKIN MODEL "C060", HIGH PERFORMANCE, AIRFOIL, OPPOSED BLADE.
10. PATCH, SEAL, AND RE-INSULATE DUCT.
11. CONNECT EXHAUST FAN TO RETURN AIR DUCT. PROVIDE NEW MANUAL BALANCING DAMPER IN RISER. BALANCE RELIEF AIR DUCT TO 1,200 CFM.
12. CONNECT EXHAUST FAN TO RETURN AIR DUCT. PROVIDE NEW MANUAL BALANCING DAMPER IN RISER. BALANCE RELIEF AIR DUCT TO 1,255 CFM.
13. CONNECT BUILDING RELIEF AIR DUCT TO EXHAUST FAN. PROVIDE NEW MANUAL BALANCING DAMPER. BALANCE RELIEF AIR DUCT TO 2,400 CFM.
14. CONNECT EXHAUST AIR DUCT TO EXHAUST FAN. PROVIDE NEW MANUAL BALANCING DAMPER. BALANCE EXHAUST AIR DUCT TO 175 CFM.
15. BALANCE BUILDING RELIEF AIR TO 1,800 CFM.
16. BALANCE BUILDING RELIEF AIR TO 1,140 CFM.

LEGEND:


- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT



DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p. 713.914.0888 f.
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002


Plotted: Apr 7, 2022, 4:17 PM by user: rhterina
 C:\Users\rhterina\OneDrive\Documents\218007.002 (PT RECOVERED FILE DO NOT DELETE).DWG

REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	ENLARGED MECHANICAL ROOM PLANS
SHEET NUMBER:	M3.13




1 LEVEL 1H MECHANICAL CHILLED WATER PLANT
 M3.13 1/4" = 1'-0"

- MECHANICAL GENERAL NOTES:**
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD. SO THEY HAVE OBTAINED THE SCOPE OF THE MECHANICAL DEMOLITION WORK INVOLVED AS A RESULT OF MODIFICATIONS TO THE EXISTING STRUCTURE, THE SCOPE OF WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT, OR APPARATUS WHICH MAY BE REROUTED, RELOCATED, OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE REROUTED OR REMOVED EITHER ACCOMPLISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON DRAWINGS, CONTRACTOR SHALL DEMOLISH ONLY WHAT IS INDICATED TO BE DEMOLISHED ON DRAWINGS.
 - CONTRACTOR SHALL COORDINATE WITH OWNER FOR ALL EQUIPMENT BEING REMOVED. OWNER SHALL RESERVE THE RIGHT TO CLAIM ALL EQUIPMENT, DUCTWORK, AND AIR DEVICES REMOVED DURING DEMOLITION.
 - CONTRACTOR TO REPORT ANY DAMAGED EQUIPMENT THAT IS SHOWN AS EXISTING TO REMAIN TO THE OWNER PRIOR TO STARTING ALL WORK. ALL EQUIPMENT FOUND TO BE DAMAGED AT THE TIME OF SUBSTANTIAL COMPLETION, THAT HAD NOT BEEN REPORTED PRIOR TO CONSTRUCTION, CONTRACTOR TO REPAIR AT THEIR OWN COST.
 - WHERE EQUIPMENT IS SCHEDULED TO BE DEMOLISHED/REMOVED AND REPLACED, THE CONTRACTOR SHALL PREP ALL OPENINGS, CONNECTIONS, FLASHING, PENETRATIONS, DUCT OR PIPING FITTINGS, ETC. TO ACCOMMODATE THE NEW EQUIPMENT. IT IS UNLIKELY THAT NEW EQUIPMENT SPECIFIED IN NEW WORK PHASE WILL DIRECTLY ALIGN WITH EXISTING CONDITIONS.
 - MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
 - MECHANICAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR PRIOR TO ACTUAL INSTALLATION OF TEMPERATURE AND HUMIDITY SENSORS.
 - ALL EQUIPMENT, DUCTWORK, CONTROLS AND ACCESSORIES FOUND TO BE ABANDONED SHALL BE REMOVED.
 - CONTRACTOR SHALL COORDINATE CONSTRUCTION WITH BUILDING FACILITY AS TO NOT DISTURB OPERATING HOURS.
 - CONTRACTOR SHALL COORDINATE CLEARANCES WITH ALL APPLICABLE TRADES TO ENSURE THAT ALL NECESSARY CODES ARE IN COMPLIANCE.

- MECHANICAL KEY NOTES:**
- AIR SEPARATOR, AS-1, SHALL BE FLOOR SUPPORTED ON EXISTING HIGH HOUSE KEEPING PAD, OFFSET AIR VENT TO MINIMIZE WATER SPILLAGE ONTO UNIT. RE: TO 16/M6.01
 - EXPANSION TANK, ET-1, SHALL BE FLOOR MOUNTED ON EXISTING HIGH HOUSEKEEPING PAD. RE: TO 16/M6.01.
 - 16" EXHAUST DUCT, DROP DOWN TO 18" ABOVE FINISHED FLOOR. TERMINATE IN BRID SCREEN. RACK TO PERIMETER WALL BALANCE INLET AT 1300 CFM.
 - PROVIDE LWR-CWP-1 & LWR-CWP-2 WITH CONTROL DAMPER. DAMPER SHALL REMAIN CLOSED UNLESS COMMANDED OPEN THRU REFRIGERANT MONITORING SYSTEM. MOUNT BOTTOM OF LOUVER AT 18" ABOVE FINISHED FLOOR (TOP OF SECOND CMU COURSE).
 - MOUNT REFRIGERANT MONITORING CONTROL PANEL (RMCP) 54" ABOVE FINISHED FLOOR TO TOP. UNIT SHALL COME COMPLETE WITH HORNS/STROBE ASSEMBLY. PROVIDE COMMUNICATIONS MODULE AS REQUIRED FOR DDC SYSTEM. INITIATION OF REFRIGERANT PURGE/ALARM CYCLE SHALL SEND AN ALARM THRU DDC. PROVIDE MANUAL RESET IN PANEL.
 - REFRIGERANT MONITORING SENSOR (RMS), MOUNT AT 18" ABOVE FINISHED FLOOR.
 - REFRIGERANT MONITORING SYSTEM HORN/STROBE. COORDINATE FINAL LOCATION WITH ARCHITECTURAL DOORS. UNIT SHALL BE WEATHER PROOF (EXTERIOR UNITS ONLY) AND MOUNTED 80" ABOVE FINISHED FLOOR. PROVIDE SIGN AT EACH LOCATION THAT READS "MACHINERY ROOM AUTHORIZED PERSONNEL ONLY". SIGN MUST ALSO INCLUDE WORDING TO PROHIBIT ENTERING MACHINERY ROOM WITHOUT PROPER PROTECTIVE EQUIPMENT DURING A REFRIGERANT ALARM CONDITION.
 - WFD SHALL BE PROVIDED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR.
 - NEW CONDENSER WATER TREATMENT PUMPS/CONTROLLER IN THIS AREA. REFER TO DETAIL 24/M6.01 FOR PIPING/EQUIPMENT REQUIREMENTS. INSTALL 4X8X3/4" TREATED PLYWOOD AT 2'-0" ABOVE FINISHED FLOOR. PAINT TO MATCH SURROUNDING WALL FINISH.
 - APPROXIMATE LOCATION OF CONDENSER WATER FLOW METER. SPECIFIC LOCATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS.
 - NEW 1-1/2" MAKEUP WATER LINE AND RPZ BACKFLOW PREVENTER.
 - SELF CONTAINED BREATHING APPARATUS IN WEATHER PROOF ENCLOSURE.
 - APPROXIMATE LOCATION OF CHILLED WATER FLOW METER. SPECIFIC LOCATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS.
 - THREE SOCK CHEMICAL FEEDER MOUNTED ON EXISTING HOUSE KEEPING PAD. REFER TO DETAIL 17/M6.01.
 - NEW MOTORIZED CONTROL VALVE EQUAL TO BRAY SERIES 70.

- LEGEND:**
- NEW PIPING AND EQUIPMENT
 - EXISTING PIPING AND EQUIPMENT



DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p 713.914.0886 f
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002





Plotted: Apr 7, 2022, 4:27 PM by user: rblakes, C:\Users\rblakes\OneDrive\Documents\218007.002\RT RECOVERED FILE DO NOT DELETE\DWG

REVISION No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2






DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	MECHANICAL CONTROLS
SHEET NUMBER:	M4.02


DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p 713.914.0888 f
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002
 HA JA JB --- --



3 Single Zone VAV Air Handling Unit - Control Schematic and Sequence of Operations
 NOT TO SCALE

AI	ANALOG INPUT	W	WALL SENSOR/THERMOSTAT
AO	ANALOG OUTPUT	CS	CARBON DIOXIDE SENSOR
SB	DIGITAL/BINARY INPUT	SP	SET POINT
SB/O	DIGITAL/BINARY OUTPUT	SA	SUPPLY AIR
MO	ON-OFF MOTORIZED DAMPER	RA	RETURN AIR
MD	MODULATING TYPE MOTORIZED DAMPER	O/A	OUTSIDE AIR
AFS	AIR FLOW MEASURING STATION	HC	HEATING COIL
MCV	CONTROL VALVE MODULATING TYPE	CC	COOLING COIL
VP	VARIABLE FREQUENCY DRIVE	DC	DIRECT EXPANSION COOLING COIL
CSR	CURRENT SENSING RELAY	PCV	PRESSURE INDEPENDENT CHARACTERIZED CONTROL VALVE
FRZ	FREEZE/STAT	AC	AIRFLOW CROSS
HSL	HIGH STATIC LIMIT	PS	DIFFERENTIAL PRESSURE SWITCH
SPT	STATIC PRESSURE TRANSMITTER		
DP	DIFFERENTIAL PRESSURE TRANSDUCER		
FM	FLOW METER		
FS	FLOW SWITCH		
DAT	DISCHARGE AIR TEMPERATURE SENSOR		





System Off - When the system is off:
 The chillers shall be off.
 The pumps shall be off.
 The bypass valve shall be closed.
 The chiller isolation valves shall be closed.
 The control loops shall be disabled.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT

System Startup - System startup shall be initiated:
 Manually by an Operator command on the chiller graphic at the EMCS.
 Automatically by the EMCS, when a call for cooling has been received.

System Operation - When system start-up has been initiated:

The outside air temperature must be above the outside air lockout setpoint, before the chiller can be activated. The number of cooling requests required and the length of time the requests must be received before activating the chiller plant shall be adjustable. The chillers and pumps shall be lead/lag and rotated weekly at a time and on a day of the week when the chiller plant is not in operation. Rotation shall be based on accumulated runtime for each type of equipment.

When the chiller plant is activated, the EMCS shall open the evaporator barrel isolation valve on the lead chiller. When the valve end switch has been proven open, the EMCS shall enable the lead pump. A current switch shall prove the pump status at the EMCS, which shall generate an alarm, if the switch is not made within 45 seconds (adjustable). There shall also be a 10 second (adjustable) de-bounce time to prevent nuisance alarms from a bouncing switch. If the pump run status is not proven, the EMCS shall discontinue the enable signal to the pump and rotate pumps. The EMCS shall then energize a lag pump to run in the same manner as described above. The lag pump shall become the lead pump.

When the lead pump status is proven, the EMCS shall enable the lead chiller. A flow switch in the chilled water piping shall complete the circuit to the chiller factory installed controller proving that evaporator flow has been established. If the chiller alarm input closes (indicating that the chiller has alarm), the EMCS shall generate an alarm, discontinue the enable signal to the lead chiller and open the evaporator barrel isolation valve on the lag chiller. When the valve end switch has been proven open, the EMCS shall close the evaporator barrel isolation valve on the failed chiller and it shall be removed from service. The lag chiller shall become the lead chiller. The chiller shall run to maintain the supply water setpoint.

The EMCS shall monitor the "Chiller Output" point from each chiller. If the point is not available, the EMCS shall monitor the kW of the chiller and calculate the Chiller Output by the equation, ((instantaneous kW / full load kW) * (nominal capacity)). The combined total Chiller Output of all operating chillers shall be the Plant Output. The combined total Nominal Capacity of all operating chillers shall be the Total Capacity. The EMCS shall monitor temperature inputs from sensors mounted in the common supply and return piping and flow meters mounted in the chiller supply piping, and calculate the building load in Tons.

If the value of ((Plant Output / Total Capacity) * 100) is greater than the stage-up setpoint for 10 minutes (adjustable) or the CHW supply temperature rises greater than 4 °F (adjustable) above setpoint, a lag chiller shall be enabled into operation. If the value of ((Plant Output / Total Capacity) * 100) is less than the stage-down setpoint for 10 minutes (adjustable), a lag chiller shall be disabled.

A differential pressure sensor monitoring the pressure between the building CHWS and CHWR piping shall be used to modulate the speed of the CHW pumps. A PID control loop shall modulate the speed of the CHW pumps from their minimum speed to their maximum speed as the differential pressure deviates from setpoint. If the differential pressure is 2 psi below setpoint and the active pumps output are above the pump stage-up setpoint for 15 minutes (adjustable), a lag pump shall be enabled. When more than one pump is operating and the active pumps output are below the pump stage-down setpoint for 15 minutes (adjustable), the lag pump shall be de-energized. All active pumps shall be modulated with the same ramp signal.

While only one chiller is in operation, the corresponding flow meter shall be used to maintain the chiller minimum flow rate by modulating the bypass valve open. The chilled water flow rate shall not change by more than 10% per minute.

The EMCS shall monitor the position of all of the chilled water valves at the units that the plant serves and the differential pressure setpoint shall be reset based on achieving a target valve position of 90%. There shall be a dead band of 5% to prevent hunting of the reset program. The differential pressure setpoint shall not change by more than 1 psi per 5 minute (adj.) interval. The target valve position, the reset time, the deadband, and the rate of change values shall be adjustable.

When a chiller is to be disabled, the EMCS shall discontinue the command for the chiller to run. The EMCS shall continue to hold open the chiller isolation valve until the chiller status has indicated that it is off. Then the EMCS shall close the valve.


When the outdoor air temperature drops below the freeze protection setpoint, the EMCS shall open the chilled water valves to 50% open (adj.) for flow through the AHU coils, the lead chiller isolation valve shall be opened and the lead chilled water pump shall be activated to run at its minimum referenced speed value until ambient temperature rises above setpoint.

The EMCS shall monitor the outside air temperature and humidity. The EMCS shall calculate the outside air enthalpy, wet bulb temperature, and dew point temperature. These values shall be displayed on all air and water systems graphics.

System Setpoints - The setpoints for the system shall be set as follows:

The outside air temperature lockout setpoint shall be 50 °F (adjustable).
 The chiller leaving water temperature setpoint shall be 42 °F (adjustable).
 The chiller stage-up setpoint shall be 90% (adjustable).
 The chiller stage-down setpoint shall be 50% (adjustable).
 The chiller minimum flow setpoint shall be established by chiller manufacturer (adjustable).
 The chilled water system differential pressure shall be initially set at 12 psi (adjustable) and shall have reset limits of 8 psi to 16 psi (adjustable).
 The pump stage-up setpoint shall be 95% (adjustable).
 The pump stage-down setpoint shall be 50% (adjustable).
 The outdoor air temperature freeze protection setpoint shall be 38 °F (adjustable).

3 Chilled Water System - Variable Primary Flow - Control Schematic and Sequence of Operations
 NOT TO SCALE



System Off - When the system is off:
 The chillers shall be off.
 The pumps shall be off.
 The fans shall be off.
 The tower bypass valves shall be closed.
 The chiller isolation valves shall be closed.
 The control loops shall be disabled.

LEGEND:

- NEW PIPING AND EQUIPMENT
- EXISTING PIPING AND EQUIPMENT

System Startup - System startup shall be initiated:
 Automatically by the EMCS, when the chiller plant is enabled.

System Operation - When system start-up has been initiated:

When the condenser water system is activated, the EMCS shall open the condenser isolation valve on the lead chiller. When the valve end switches have been proven open, the EMCS shall send an enable signal to the lead pump. A current switch shall prove the pump status at the EMCS, which shall generate an alarm, if the switch is not made within 45 seconds (adjustable). There shall also be a 10 second (adjustable) de-bounce time to prevent nuisance alarms from a bouncing switch. If the pump run status is not proven, the EMCS shall discontinue the enable signal to the pump and rotate pumps. The EMCS shall then energize a lag pump to run in the same manner as described above. That pump shall become the lead pump.

When the lead pump status is proven, the EMCS shall enable the lead chiller. A flow switch in the condenser water piping shall complete the circuit to the chiller factory installed controller proving that flow has been established. If the chiller alarm input closes (indicating that the chiller has alarm), the EMCS shall generate an alarm, discontinue the enable signal to the lead chiller and open the condenser isolation valve on the lag chiller. When the valve end switch has been proven open, the EMCS shall close the condenser isolation valve on the failed chiller and it shall be removed from service. The lag chiller shall become the lead chiller. When more than one chiller is operating, the corresponding number of condenser pumps and cooling towers shall be enabled. The speed reference of the condenser water pumps shall be determined by TAB and set by the EMCS, refer to pump schedule for GPM values.

Two towers shall enable during plant operation except as follows:

1. A failure of either tower.
2. A low load condition in which both towers provide a condenser water supply below 50 °F (see tower sequence below).

Both towers shall operate in parallel to maintain a condenser water supply temperature equal to the lesser of 85 °F or 5 °F above ambient wet bulb temperature. If both towers in operation provide a condenser water supply that reaches 50 °F (or recommended by chiller manufacturer), the lag tower shall be disabled. Single tower operation shall continue to maintain 50 °F. If the lead tower becomes disabled and CWC falls below 50 °F, condenser water bypass valve shall modulate open to maintain 50 °F. As condenser water temperature increases, sequence shall be reversed until both towers are again operational.

Condenser water pumps shall be operated to have speed controlled based upon Testing, Adjusting, and Balancing. When a single chiller and condenser water pump are operating, the lead pump shall provide 660 GPM. When both chillers and condenser water pumps are operating, two condenser water pumps shall operate together to provide 1320 GPM.

The EMCS shall calculate the outside air enthalpy, wet bulb temperature, and dew point temperature. These values shall be displayed on all air and water systems graphics.

System Alarms - The EMCS shall generate an alarm as follows:

- Bypass Valve failure: Commanded open but the status is off.
- Fan Failure: Commanded on but the status is off.
- Vibration Cutout Switch: When tower vibration cutout switch signals a tower fan shutdown.
- High Condenser Water Supply (Basin) Temp: If greater than 88 °F (adjustable).
- Low Condenser Water Supply (Basin) Temp: If less than 37 °F (adjustable).
- High Condenser Water Return Temp: If greater than 100 °F (adjustable).

1 Condenser Water System - Chiller Plant - Control Schematic and Sequence of Operations
 NOT TO SCALE

AI	ANALOG INPUT	CS	WALL SENSOR/THERMOSTAT
AO	ANALOG OUTPUT	CO2	CARBON DIOXIDE SENSOR
DI	DIGITAL/BINARY INPUT	SP	SET POINT
DO	DIGITAL/BINARY OUTPUT	S/A	SUPPLY AIR
MO	ON-OFF MOTORIZED DAMPER	R/A	RETURN AIR
MD	MODULATING TYPE MOTORIZED DAMPER	O/A	OUTSIDE AIR
AFMS	AIR FLOW MEASURING STATION	HC	HEATING COIL
CMV	CONTROL VALVE MODULATING TYPE	CC	COOLING COIL
VP	VARIABLE FREQUENCY DRIVE	DC	DIRECT EXPANSION COOLING COIL
CR	CURRENT SENSING RELAY	PCV	PRESSURE INDEPENDENT CHARACTERIZED CONTROL VALVE
FZ	FREESTAT	AC	AIRFLOW CROSS
HL	HIGH STATIC LIMIT	PS	DIFFERENTIAL PRESSURE SWITCH
SP1	STATIC PRESSURE TRANSMITTER		
DPT	DIFFERENTIAL PRESSURE TRANSDUCER		
FM	FLOW METER		
FS	FLOW SWITCH		
DAT	DISCHARGE AIR TEMPERATURE SENSOR		

2 CONTROL SCHEMATIC LEGEND
 NOT TO SCALE

Plotted: Aug 7, 2022 4:12 PM by user: dbcr, Sheet: 4/7/2022, by user: dbcr, C:\Users\jenina\OneDrive\Documents\218007_002-DETAILS AND SCHEDULES.dwg



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
 MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE: 4/7/2022
 DRAWN BY: DBR
 CHECKED BY: DBR
 PROJECT NUMBER: 218007.002
 SHEET TITLE:

MECHANICAL CONTROLS

SHEET NUMBER:

M4.03



DBR Project Number: 218007.002
 HA JA JB ---

LOUVER SCHEDULE									
MARK	SERVES	CFM	WIDTH (IN)	HEIGHT (IN)	MINIMUM FREE AREA (F ²)	MAX. PRESSURE DROP AT 750 FPM INTAKE (" w.g.)	MANUF.	MODEL	NOTES
LVR-CUP-1	RMS PURGE INTAKE	1300	24	30	1.73	0.08	EVH-5010		ALL
LVR-CUP-2	RMS PURGE INTAKE	1300	24	30	1.73	0.08	EVH-5010		ALL
LVR-AHU-22	AHU-21 & AHU-22	615	24	16	0.82	0.08	EVH-5010		ALL

NOTES:
1. FINISH SHALL BE RYMAR 500 FINISH. PAINT COLOR BY ARCHITECT. COORDINATE FINAL ELEVATION WITH ARCHITECT.
2. LOUVER SHALL MEET AMCA 550 AND AMCA 540.

VARIABLE FREQUENCY DRIVE SCHEDULE

MARK	SERVES	EQUIP	HP	INPUT VOLT	OUTPUT VOLT	MOUNTING	ENCLOSURE	MANUF.	MODEL	NOTES
VFD-AHU-1+1-1	AHU-1+2 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-1+2-2	AHU-1+2 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-3-1	AHU-3 SUPPLY FAN	AHU	7.5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-3-2	AHU-3 SUPPLY FAN	AHU	7.5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-4+1-1	AHU-4+5 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-4+2-2	AHU-4+5 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-6+1-1	AHU-6+7 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-6+2-2	AHU-6+7 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-8-1	AHU-8 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-8-2	AHU-8 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-9	AHU-9 SUPPLY FAN	AHU	3	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-10-1	AHU-10 SUPPLY FAN	AHU	7.5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-10-2	AHU-10 SUPPLY FAN	AHU	7.5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-11	AHU-11 SUPPLY FAN	AHU	3	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-12-1	AHU-12 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-12-2	AHU-12 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-13-1	AHU-13 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-13-2	AHU-13 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-14	AHU-14 SUPPLY FAN	AHU	3	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-15	AHU-15 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-16	AHU-16 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-18-1	AHU-18 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-AHU-18-2	AHU-18 SUPPLY FAN	AHU	5	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-CHWP-1	CHWP-1	PUMP	30	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-CHWP-2	CHWP-2	PUMP	30	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL
VFD-CHWP-3	CHWP-3	PUMP	30	460/3	460/3	WALL	NEMA 12	DANFOSS	VLT HVAC	ALL

NOTES:
1. VFD SHALL BE PROVIDED AND MOUNTED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR.
2. PROVIDE WITH BACKET INTERFACE.
3. PROVIDE VFD WITH NON-FUSED DISCONNECT

PUMP SCHEDULE

MARK	CHWP-1	CHWP-2	CHWP-3
	CHILLED WATER	CHILLED WATER	CHILLED WATER
TYPE	END SUCTION	END SUCTION	END SUCTION
DESIGN FLOW RATE (GPM)	528	528	528
MINIMUM FLOW RATE (GPM)	125.0	125.0	125.0
DYNAMIC HEAD-FT	130	130	130
MOTOR RPM	1800	1800	1800
MIN. PUMP EFF. (%)	74.7	74.7	74.7
NPSH MAX. REQUIRED	7.980	7.980	7.980
HORSEPOWER	30	30	30
VOLTS/PHASE/HERTZ	460/3/60	460/3/60	460/3/60
MANUFACTURER	BELL & GOSSETT	BELL & GOSSETT	BELL & GOSSETT
MODEL	e-1510 3GB	e-1510 3GB	e-1510 3GB
NOTES	ALL	ALL	ALL

NOTES:
1. PUMP SHALL BE NON-OVERLOADING ACROSS ENTIRE GPM RANGE.
2. PROVIDE WITH REMOTE MOUNTED VARIABLE FREQUENCY DRIVE.
3. PROVIDE WITH PREMIUM EFFICIENCY QDP MOTOR FOR OPERATION WITH VARIABLE FREQUENCY DRIVE.
4. PROVIDE WITH INDUCTIVE ABSORBERS

AIR SEPARATOR SCHEDULE

MARK	AS-1
SERVICE	CHILLED WATER SYSTEM
MAX FLOW (GPM)	1,056
INLET / OUTLET SIZE (INCHES)	10
SHIPPING WEIGHT (LBS)	311
FLOODED WEIGHT (LBS)	834
MANUFACTURER	Bell & Gossett
MODEL	CRSA-10F
NOTES	ALL

NOTES:
1. PROVIDE HIGH CAPACITY AIR VENT. AIR VENT SHALL BE PIPED OFFSET FROM SEPARATOR TO MINIMIZE CORROSION CAUSED BY WATER DRIPS.

EXPANSION TANK SCHEDULE

MARK	ET-1
SERVICE	CHILLED WATER
TANK VOLUME (GALLONS)	80
MAX. ACCEPTANCE	27
MIN. OPERATING PRESSURE (PSI)	60.0
MAX. OPERATING PRESSURE (PSI)	80
TYPE	BLADDER
MANUFACTURER	BELL AND GOSSETT
MODEL NO.	B-300LA
NOTES	1

NOTES:
1. PROVIDE AUTOMATIC AIR VENT.

SINGLE INLET VAV BOX WITH REHEAT SCHEDULE

MARK	COOLING CFM		HEATING CFM		REHEAT KW	INLET SIZE	VOLTS/PHASE/Hz	MANUFACTURER	MODEL
	MAX	MIN	MAX	MIN					
VAV-1-01	840	255	420	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-02	840	255	420	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-03	840	255	420	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-04	960	290	480	290	6	10"Ø	480/3/60	PRICE	SDV
VAV-1-05	1,750	525	875	525	10	14"Ø	480/3/60	PRICE	SDV
VAV-1-06	980	295	490	295	6	10"Ø	480/3/60	PRICE	SDV
VAV-1-07	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-08	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-09	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-1-10	740	225	370	225	5	10"Ø	277/1/60	PRICE	SDV
VAV-2-01	470	145	235	145	3	8"Ø	277/1/60	PRICE	SDV
VAV-2-02	2,100	630	1050	630	12	16"Ø	480/3/60	PRICE	SDV
VAV-2-03	800	180	300	180	4	8"Ø	277/1/60	PRICE	SDV
VAV-3-01	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-02	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-3-03	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-3-04	1,550	465	775	465	9	12"Ø	480/3/60	PRICE	SDV
VAV-3-05	850	255	425	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-06	850	255	425	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-07	850	255	425	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-08	850	270	445	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-09	850	255	425	255	5	10"Ø	277/1/60	PRICE	SDV
VAV-3-10	850	260	430	260	5	10"Ø	277/1/60	PRICE	SDV
VAV-4-01	500	150	250	150	3	8"Ø	277/1/60	PRICE	SDV
VAV-4-02	500	150	250	150	3	8"Ø	277/1/60	PRICE	SDV
VAV-4-03	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-4-04	1,500	450	750	450	9	12"Ø	480/3/60	PRICE	SDV
VAV-4-05	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-4-06	500	150	250	150	3	8"Ø	277/1/60	PRICE	SDV
VAV-5-01	3,020	910	1510	910	17	16"Ø	480/3/60	PRICE	SDV
VAV-6-01	2,730	820	1365	820	16	16"Ø	480/3/60	PRICE	SDV
VAV-7-01	875	265	440	265	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-02	875	265	440	265	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-03	875	265	440	265	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-04	875	265	440	265	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-05	960	290	480	290	6	10"Ø	480/3/60	PRICE	SDV
VAV-7-06	1,880	565	940	565	11	14"Ø	480/3/60	PRICE	SDV
VAV-7-07	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-08	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-09	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-7-10	960	290	480	290	6	10"Ø	480/3/60	PRICE	SDV
VAV-8-01	1,940	585	970	585	11	14"Ø	480/3/60	PRICE	SDV
VAV-9-02	2,000	600	1000	600	12	14"Ø	480/3/60	PRICE	SDV
VAV-9-03	1,100	330	550	330	7	12"Ø	480/3/60	PRICE	SDV
VAV-9-04	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-9-05	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-9-06	960	290	480	290	6	10"Ø	480/3/60	PRICE	SDV
VAV-9-07	2,200	660	1100	660	13	16"Ø	480/3/60	PRICE	SDV
VAV-9-08	2,000	600	1000	600	12	14"Ø	480/3/60	PRICE	SDV
VAV-9-09	1,050	315	525	315	6	10"Ø	480/3/60	PRICE	SDV
VAV-9-10	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-9-13	1,450	435	725	435	9	12"Ø	480/3/60	PRICE	SDV
VAV-9-14	500	150	250	150	3	8"Ø	277/1/60	PRICE	SDV
VAV-10-01	1,135	345	570	345	7	12"Ø	480/3/60	PRICE	SDV
VAV-10-02	1,250	375	625	375	7	12"Ø	480/3/60	PRICE	SDV
VAV-10-03	1,100	330	550	330	7	12"Ø	480/3/60	PRICE	SDV
VAV-10-04	1,250	375	625	375	7	12"Ø	480/3/60	PRICE	SDV
VAV-10-05	1,330	400	665	400	8	12"Ø	480/3/60	PRICE	SDV
VAV-10-06	1,630	490	815	490	10	14"Ø	480/3/60	PRICE	SDV
VAV-10-07	1,250	375	625	375	7	12"Ø	480/3/60	PRICE	SDV
VAV-10-08	1,250	375	625	375	7	12"Ø	480/3/60	PRICE	SDV
VAV-11-01	1,100	330	550	330	7	12"Ø	480/3/60	PRICE	SDV
VAV-11-02	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-11-03	1,100	330	550	330	7	12"Ø	480/3/60	PRICE	SDV
VAV-11-04	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-11-05	500	150	250	150	3	8"Ø	277/1/60	PRICE	SDV
VAV-12-01	2,100	630	1050	630	12	16"Ø	480/3/60	PRICE	SDV
VAV-12-02	900	270	450	270	5	10"Ø	277/1/60	PRICE	SDV
VAV-12-03	1,000	300	500	300	6	10"Ø	480/3/60	PRICE	SDV
VAV-12-04	2,175	655	1090	655	13	16"Ø	480/3/60	PRICE	SDV
VAV-12-05	1,250	375	625	375	7	12"Ø	480/3/60	PRICE	SDV
VAV-13-01	950	285	475	285	6	10"Ø	480/3/60	PRICE	SDV
VAV-13-02	1,710	515	855	515	10	14"Ø	480/3/60	PRICE	SDV
VAV-13-03									

REVISION No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE: 4/7/2022
 DRAWN BY: DBR
 CHECKED BY: DBR
 PROJECT NUMBER: 218007.002
 SHEET TITLE: MECHANICAL DETAILS

DBR
 9990 Richmond Avenue, Suite 300
 Houston, Texas 77042
 713.914.0888 f 713.914.0886 f
 TBE Firm Registration No. 2234
 DBR Project Number: 218007.002


M6.01




1 TYP. MEP INSTALLATION DETAIL
 NOT TO SCALE




6 CONDENSING UNIT ROOF MOUNTED
 NOT TO SCALE




2 REFRIGERANT PIPING SCHEMATIC
 NOT TO SCALE




3 CENTRIFUGAL ROOF EXHAUST FAN
 NOT TO SCALE




4 INTAKE LOUVER MOUNTING
 NOT TO SCALE




7 CONDENSING UNIT MOUNTING ON GRADE
 NOT TO SCALE




11 EXPOSED RECT. DUCT ON ROOF
 NOT TO SCALE




13 DUCT SUPPORT ON ROOF
 NOT TO SCALE




14 ELECTRIC DUCT HEATER
 NOT TO SCALE




15 WATER COOLED CHILLER
 NOT TO SCALE




11 RECTANGULAR BRANCH DUCT TAP
 NOT TO SCALE




16 EXPANSION TANK/ MAKE-UP WATER PIPING DETAIL
 NOT TO SCALE




13 EXPOSED RECT. DUCT ON ROOF
 NOT TO SCALE




14 ELECTRIC DUCT HEATER
 NOT TO SCALE




15 WATER COOLED CHILLER
 NOT TO SCALE




16 EXPANSION TANK/ MAKE-UP WATER PIPING DETAIL
 NOT TO SCALE




13 EXPOSED RECT. DUCT ON ROOF
 NOT TO SCALE




14 ELECTRIC DUCT HEATER
 NOT TO SCALE




15 WATER COOLED CHILLER
 NOT TO SCALE




20 PIPE HANGER DETAIL (4-PIPE)
 NOT TO SCALE




21 CONDENSATE DRAIN THRU CURB
 NOT TO SCALE




22 FLOOR MOUNTED REFR. PIPE
 NOT TO SCALE




18 AIR SEPARATOR MOUNTING
 NOT TO SCALE




24 CONDENSER WATER TREATMENT
 NOT TO SCALE




25 PIPE HANGER DETAIL
 NOT TO SCALE




26 COOLING COIL CONDENSATE DRAIN
 NOT TO SCALE



27 PIPE HANGER DETAIL (1-PIPE)
 NOT TO SCALE




24 2-WAY CONTROL VALVE AND COIL PIPING
 NOT TO SCALE



29 EXISTING ROOF PIPE PENETRATION
 NOT TO SCALE

Project: 4-7-2022 - 4.0 PM HVAC Improvements - Sched. 4/7/2022 by user: electric
 C:\Users\rtjerner\OneDrive\Documents\218007.002\Drawings\01\218007.002-DETAILS AND SCHEDULES.dwg

Plotted: Apr 7, 2022, 3:38 PM by user: jbd@db... - Sheet: 4/8/2022 by user: jbd@...
 C:\Users\jbd@db... \AppData\Local\Temp\Drawings\EP2-218007-01.dwg



1 LEVEL 1 ELECTRICAL POWER PLAN - C
 EP2.11C 1/8" = 1'-0"

GENERAL ELECTRICAL NOTES:

- A. CONTRACTOR SHALL VERIFY MECHANICAL EQUIPMENT CONNECTION LOCATION WITH FURNISHED EQUIPMENT.
- B. CONTRACTOR SHALL PROVIDE HANDLE TIES MANUFACTURED BY THE SWITCH GEAR SUPPLIER ON ALL MULTI-WIRE CIRCUITS TO MEET THE REQUIREMENTS OF ARTICLE 210.4(B) OF THE 2014 NEC. AT THE CONTRACTOR'S OPTION, TWO AND THREE POLE BREAKERS MAY BE USED.
- C. ALL VAV BOXES ARE SUPPLIED WITH INTEGRAL DISCONNECT SWITCH. VERIFY EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- D. CONTRACTOR SHALL NOTE THAT ALL MATERIALS BEING USED WITHIN THE CEILING PLENUM MUST BE PLENUM RATED.

ELECTRICAL KEYED NOTES

- ① VFD, VERIFY EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL. VFD SHALL BE PROVIDED AND INSTALLED BY MECHANICAL, WIRED BY ELECTRICAL. VFD SHALL SERVE AS DISCONNECTING MEANS.
- ② DISCONNECT SWITCH PROVIDED WITH EQUIPMENT. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- ③ FIELD COORDINATE EXACT LOCATION TO PROVIDE CODE REQUIRED CLEARANCE.



REVISION No.	DATE	DESCRIPTION
01	5/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	

LEVEL 1
 ELECTRICAL
 POWER PLAN - C

SHEET NUMBER:

EP2.11C

Plotted: Apr 7, 2022, 3:40 PM by user: jbd@db - Sheet: 4/8/2022 by user: jbd@db
 C:\Users\jbd@db\OneDrive\Documents\218007.002 - EP2.12G - District Wide HVAC Improvements - MMS\Project Files\Drawings\EP2.12G\07-01.dwg



GENERAL ELECTRICAL NOTES:


- A. CONTRACTOR SHALL VERIFY MECHANICAL EQUIPMENT CONNECTION LOCATION WITH FURNISHED EQUIPMENT.
- B. CONTRACTOR SHALL PROVIDE HANDLE TIES MANUFACTURED BY THE SWITCH GEAR SUPPLIER ON ALL MULTI-WIRE CIRCUITS TO MEET THE REQUIREMENTS OF ARTICLE 210.4(B) OF THE 2014 NEC. AT THE CONTRACTOR'S OPTION, TWO AND THREE POLE BREAKERS MAY BE USED.
- C. ALL VAV BOXES ARE SUPPLIED WITH INTEGRAL DISCONNECT SWITCH. VERIFY EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- D. CONTRACTOR SHALL NOTE THAT ALL MATERIALS BEING USED WITHIN THE CEILING PLENUM MUST BE PLENUM RATED.

ELECTRICAL KEYED NOTES

- ① INTERNALLY MOUNTED DISCONNECT SWITCH PROVIDED WITH EQUIPMENT. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FURNISHED EQUIPMENT.
- ② 3/2" Ø, #6GND, 2" C TO EXISTING CAFETERIA SWITCHBOARD-KP. PROVIDE NEW 175A/3P BREAKER IN SWITCHBOARD-KP.
- ③ 30A/3P/25AF/N1 DISCONNECT SWITCH. PROVIDE CODE REQUIRED MOUNTING AND CLEARANCE. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- ④ 30A/3P/15AF/N1 DISCONNECT SWITCH. PROVIDE CODE REQUIRED MOUNTING AND CLEARANCE. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- ⑤ 3/10, #10GND, 3/4" C TO EXISTING CAFETERIA SWITCHBOARD-KP. PROVIDE NEW 25A/3P BREAKER IN SWITCHBOARD-KP.
- ⑥ 3/12, #12GND, 3/4" C TO EXISTING CAFETERIA SWITCHBOARD-KP. PROVIDE NEW 15A/3P BREAKER IN SWITCHBOARD-KP.
- ⑦ 60A/3P/60AF/N3R DISCONNECT SWITCH. PROVIDE CODE REQUIRED MOUNTING AND CLEARANCE. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- ⑧ 3/16, #10GND, 1" C TO EXISTING PANEL-CK. REPLACE EXISTING BREAKER WITH NEW 60A/3P BREAKER IN EXISTING PANEL-CK.
- ⑨ 60A/3P/35AF/N3R DISCONNECT SWITCH. PROVIDE CODE REQUIRED MOUNTING AND CLEARANCE. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL.
- ⑩ 3/16, #10GND, 1" C TO EXISTING PANEL-CK. REUSE EXISTING 35A/3P BREAKER IN EXISTING PANEL-CK.
- ⑪ 3/16, #10GND, 1" C TO EXISTING SWITCHBOARD KP. PROVIDE NEW 60A/3P BREAKER IN EXISTING SWITCHBOARD KP.
- ⑫ 3/16, #10GND, 1" C TO EXISTING SWITCHBOARD KP. PROVIDE NEW 50A/3P BREAKER IN EXISTING SWITCHBOARD KP.




REVISION		
No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542


1 LEVEL 1 ELECTRICAL POWER PLAN - G
 EP2.12G 1/8" = 1'-0"



TRUE NORTH
 PLAN NORTH
DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p 713.914.0886 f
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002
 HA JA JB ---


DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	LEVEL 1 ELECTRICAL POWER PLAN - G
SHEET NUMBER:	EP2.12G

REVISION No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




ELECTRICAL KEYED NOTES


- 1 CONTRACTOR SHALL DISCONNECT AND REMOVE ALL ELECTRICAL ASSOCIATED WITH EXISTING EQUIPMENT TO BE REMOVED. DISCONNECT AND REMOVE EXISTING CONDUIT AND WIRE BACK TO SOURCE.
- 2 CONTRACTOR SHALL DISCONNECT AND REMOVE ALL ELECTRICAL ASSOCIATED WITH EXISTING BOILER EQUIPMENT TO BE REMOVED. DISCONNECT AND REMOVE ALL EXISTING CONDUIT AND WIRE.
- 3 HOMERUN TO MAIN SWITCHBOARD 'MSB'. SEE ONE-LINE DIAGRAM FOR CIRCUIT INFORMATION.
- 4 VFD PROVIDED AND INSTALLED BY MECHANICAL. WIRED BY ELECTRICAL. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL CONTRACTOR.
- 5 MOTORIZED DAMPER. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH MECHANICAL CONTRACTOR.
- 6 2#12, #12G, 3/4" TO PANEL 'L'. PROVIDE 20A/1P BREAKER.
- 7 2#10, #10G, 3/4" TO PANEL 'L'. PROVIDE 25A/1P BREAKER.
- 8 NEW MOTORIZED VALVE AT EXISTING CHILLER. COORDINATE EXACT LOCATION WITH MECHANICAL.



1 CENTRAL PLANT ENLARGED DEMOLITION POWER PLAN
 E3.01 1/4" = 1'-0"



2 CENTRAL PLANT ENLARGED POWER PLAN
 E3.01 1/4" = 1'-0"




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	ELECTRICAL ENLARGED POWER PLANS

ELECTRICAL ENLARGED POWER PLANS


SHEET NUMBER:

E3.01



DBR
 9990 Richmond Avenue, South Building, Suite 300
 Houston, Texas 77042
 713.914.0888 p 713.914.0886 f
 TBPE Firm Registration No. 2234
 DBR Project Number 218007.002
 HA JA JB

REVISION No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2




EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE: 4/7/2022
 DRAWN BY: DBR
 CHECKED BY: DBR
 PROJECT NUMBER: 218007.002
 SHEET TITLE:


ELECTRICAL ONE-LINE DIAGRAM

SHEET NUMBER: **E4.01**




1 ONE-LINE DIAGRAM - SWITCHBOARD 'MSB' - EXISTING CONDITIONS
N.T.S.

- ONE-LINE GENERAL NOTES:**
- DASHED ITEMS ARE EXISTING TO REMAIN, UNLESS NOTED OTHERWISE.
 - SOLID LINES ARE NEW WORK.
 - ALL CONDUCTORS SHALL BE COPPER.
 - CONTRACTOR SHALL INSTALL FEEDERS BASED ON THE OVERCURRENT DEVICE RATING UNLESS OTHERWISE NOTED. CONTRACTOR SHALL REFER TO THE FEEDER SCHEDULE TO OBTAIN AND INSTALL THE FEEDERS REQUIRED.
 - SERVICE EQUIPMENT IN OTHER THAN CHILLING UNITS SHALL BE LEGIBLY MARKED IN THE FIELD WITH THE MAXIMUM AVAILABLE FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE 2" X 3" IN SIZE AND SHALL BE BLUE LETTERING ON A CONTRASTING BACKGROUND. THIS LABEL SHALL ALSO INCLUDE THE DATE OF THE CALCULATION.
 - A PERMANENTLY AFFIXED LABEL SHALL BE APPLIED WITH THE AVAILABLE FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE 2" X 3" IN SIZE AND SHALL BE BLUE LETTERING ON A CONTRASTING BACKGROUND. THIS LABEL SHALL ALSO INCLUDE THE DATE OF THE CALCULATION.
 - NEW BREAKERS SHALL BE OF THE SAME MANUFACTURER AS THE EXISTING SWITCHBOARD OR PANEL IN WHICH THEY ARE INSTALLED.
 - SEE SHEET 64.02 FOR FEEDER SCHEDULE.



2 ONE-LINE DIAGRAM - SWITCHBOARD 'MSB' - NEW CONDITIONS
N.T.S.

- EXISTING CONDUIT AND WIRE TO BE DISCONNECTED AND REMOVED.
- EXISTING BREAKER TO BE REPLACED.
- PROVIDE NEW BREAKER, SIZE AS SHOWN.
- NEW 100A FEEDER, PROVIDE NEW 100A/3P BREAKER IN EXISTING PANEL. SEE FEEDER SCHEDULE FOR FEEDER SIZE.
- NEW 150A FEEDER, PROVIDE NEW 150A/3P BREAKER IN EXISTING PANEL. SEE FEEDER SCHEDULE FOR FEEDER SIZE.
- NEW 200A FEEDER, PROVIDE NEW 200A/3P BREAKER IN EXISTING PANEL. SEE FEEDER SCHEDULE FOR FEEDER SIZE.
- NEW VFD PROVIDED AND INSTALLED BY MECHANICAL, WIRED BY ELECTRICAL.



9990 Richmond Avenue, South Building, Suite 300
Houston, Texas 77042
713.914.0888 p. 713.914.0886 f.
TBPE Firm Registration No. 2234

DBR Project Number: 218007.002

HA JA JB

Plotted: Apr 7, 2022, 3:00 PM by user: jhubb. Source: 4/8/2022 by user: jhubb.
 C:\Users\jhb\ACD\Documents\DBR Inc\218007.002 - EDINB - District Wide HVAC Improvements - MMS\Project Files\Drawings\418007-DETAILS AND SCHEDULES.dwg

Plotted: Apr 7, 2022, 3:03 PM by user: jrb...
 C:\Users\jrb\OneDrive\Documents\218007.002 - EDHSD - District 10 - HVAC Improvements - MMS\Project Files\Drawings\ME-218007-DETAILS AND SCHEDULES.dwg

Panelboard MG1												85,000 AIC Rating Existing	
277/480 Volt, 3-Phase, 4-Wire 1-Section 1-Nema Rating												X New	
Notes	Load (VA)	Description	Type	Wire	CB	CKT #	CB	Wire	Type	Description	Load (VA)	Notes	
		SPARE		12	20/3	3	B 4	30/3	10				
997		AHU-14	F	12	15/3	7	A 8	15/3	12	F	1634		
12666		EDH-1	H	6	60/3	15	B 16	60/3	6	H	12000		
12666		EDH-2	H	6	60/3	21	B 22	60/3	6	H	12000		
12666		EDH-3	H	6	60/3	27	B 28	150/3	1/0	SP	39051		
Subtotal											164,055		
N.E.C. (2011)												N.E.C. (2011)	
220.44	(R) Recept.	0	0	0	220.12	(L) Lighting	0	125%	0				
220.56	(K) Kitchen	0	100%	0	220.12	(EL) Ext. Ltg.	0	125%	0				
220.60	(C) Cooling	0	0%	0	620.14	(E) Elevators	0	100%	0				
220.60	(H) Heating	185,994	100%	185,994	(WH) Water Ht.	0	100%	0					
220.60	(F) Fans	7,893	100%	7,893	(MT) Lrg. Mot.	0	125%	0					
630.11	(W) Welders	0	0	0	(SP) Sub Panel	107,153	100%	107,153					
	(M) Misc.	0	100%	0									
Total Connected Load =				301,040 VA =				362.3 AMPS				Location of Panel:	
Total Load (Diversified) =				301,040 VA =				362.3 AMPS					

Panelboard MF1												85,000 AIC Rating Existing	
277/480 Volt, 3-Phase, 4-Wire 1-Section 1-Nema Rating												X New	
Notes	Load (VA)	Description	Type	Wire	CB	CKT #	CB	Wire	Type	Description	Load (VA)	Notes	
	5000	VAV-16-01	H	10	25/1	1	A 2		H		2333		
	5000	VAV-16-02	H	10	25/1	3	B 4	20/3	12	H	2333		
	2000	VAV-16-03	H	12	20/3	7	A 8		H		3000		
	2000	VAV-16-04	H	10	25/1	11	C 12		H		3000		
	5000	VAV-16-05	H	10	25/1	13	A 14		H		2666		
	1634	AHU-16	F	12	15/3	17	C 18		H		2666		
	1634	AHU-17	F	12	15/3	23	C 24		H		4000		
	1108	ACCU-17A	C	12	15/3	29	C 30		F		1634		
	1108	ACCU-17B	C	12	15/3	33	B 34	15/3	12	F	1634		
	2521	SPACE				37	A 38				4000		
	2521	SPACE				39	B 40	20/3	12		4000		
	2521	SPACE				41	C 42				4000		
Subtotal											57,801		
N.E.C. (2011)												N.E.C. (2011)	
220.44	(R) Recept.	0	0	0	220.12	(L) Lighting	0	125%	0				
220.56	(K) Kitchen	0	100%	0	220.12	(EL) Ext. Ltg.	0	125%	0				
220.60	(C) Cooling	15,126	0%	0	620.14	(E) Elevators	0	100%	0				
220.60	(H) Heating	61,997	100%	61,997	(WH) Water Ht.	0	100%	0					
220.60	(F) Fans	18,030	100%	18,030	(MT) Lrg. Mot.	0	125%	0					
630.11	(W) Welders	0	0	0	(SP) Sub Panel	0	100%	0					
	(M) Misc.	0	100%	0									
Total Connected Load =				95,153 VA =				114.5 AMPS				Location of Panel:	
Total Load (Diversified) =				80,027 VA =				96.3 AMPS					



REVISION No.	DATE	DESCRIPTION
01	3/23/2022	ADDENDUM #1
02	4/7/2022	ADDENDUM #2



EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT
 MEMORIAL MS - HVAC IMPROVEMENTS
 3105 N DOOLITTLE RD, EDINBURG, TX 78542

DATE:	4/7/2022
DRAWN BY:	DBR
CHECKED BY:	DBR
PROJECT NUMBER:	218007.002
SHEET TITLE:	ELECTRICAL SCHEDULES
SHEET NUMBER:	E5.02

DBR Project Number	218007.002			
HA	JA	JB	---	---